

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	1-3-K	ROCK ISLAND	476	52
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

ITEM NO.	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	TOTAL PRICE	ITEM NO.	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	TOTAL PRICE	
60500080	REMOVING CATCH BASINS TO MAINTAIN FLOW	EACH				60900315	TYPE D INLET BOX, STANDARD 609006	EACH				
	TRINITY DRIVE						MILAN BELTWAY					
	LT. & RT. STA. 1+62	2					LT. STA. 356+91		1			
							RT. STA. 356+91		1			
	TOTAL	2					TOTAL		2			
60500105	FILLING MANHOLES	EACH				60900515	CONCRETE THRUST BLOCKS	EACH				
	52ND AVENUE						MILAN BELTWAY					
	38' LT. STA. 1164+90	1					RT. STA. 364+00		1			
	50' LT. STA. 1164+90	1					BLACKHAWK ROAD					
	47' LT. STA. 1167+44	1					LT. STA. 1154+00		1			
	37' LT. STA. 1167+55	1					LT. STA. 1154+00		1			
	31' LT. STA. 1170+40	1					52ND AVENUE					
	13' RT. STA. 1171+30	1					LT. STA. 1157+93.50		1			
							RT. STA. 1160+75		1			
	TOTAL	6					LT. STA. 1160+75		1			
60600095	CLASS SI CONCRETE (OUTLET)	C. Y.					RT. STA. 1163+00		1			
	RAMP 3						LT. STA. 1163+25		1			
	27' LT. STA. 15+34.54-12' LT. STA. 15+79.46	3.92					RT. STA. 1164+55		1			
							LT. STA. 1165+50		1			
	RAMP 4						LT. STA. 1167+50		1			
	29' LT. STA. 2+74.81-12' LT. STA. 2+35.41	3.92					RAMP 1					
							RT. STA. 1+37.50		1			
	TOTAL	7.84					VALLEY VIEW					
60600605	CONCRETE CURB, TYPE B	FT.					RT. STA. 152+75		1			
	44TH STREET						RT. STA. 154+00		1			
	RT. STA. 17+61.58-18+32.17	79.1					RT. STA. 155+50		1			
	C.E. LT. STA. 17+02	20.0					RT. STA. 157+75		1			
							RT. STA. 160+15		1			
	44TH STREET CONNECTOR						LT. STA. 160+15		1			
	LT. STA. 0+65.72-1+70.55	127.9					RT. STA. 161+50		1			
							LT. STA. 161+50		1			
	TOTAL	227.0					RT. STA. 163+25		1			
60605000	COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.24	FT.					LT. STA. 163+25		1			
	JOHN DEERE ROAD						RT. STA. 165+00		1			
	STAGE 2 PHASE 3						LT. STA. 165+00		1			
	LT. STA. 417+10-176+51	293.5					TOTAL		24			
							63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FT.			
	JOHN DEERE ROAD							MILAN BELTWAY				
	STAGE 2 PHASE 4							RT. STA. 356+96.53-363+90.56		694.0		
	RT. STA. 415+45-416+55	110.0						LT. STA. 357+13.92-364+11.13		697.2		
								JOHN DEERE ROAD				
	BLACKHAWK ROAD							RT. STA. 381+49.56-381+74.56		25.0		
	LT. STA. 1144+42-1150+52.2	633.6						LT. STA. 381+96.82-383+46.82		150.0		
	RT. STA. 1146+00-1156+47.4	1,012.3						52ND AVENUE				
	RT. & LT. STA. 1152+53.57-1156+74.39	835.7						RT. STA. 1157+65.14-1158+02.64		37.5		
	LT. STA. 1156+85-1157+00	22.3						LT. STA. 1157+21.71-1157+96.71		75.0		
	RT. STA. 1157+00 (E. RADIUS)	125.8						RT. STA. 1160+48.33-1161+85.83		137.5		
								LT. STA. 1160+40.76-1163+40.76		300.0		
	52ND AVENUE							TOTAL		2,116.2		
	RT. STA. 1157+25-1157+78.8	53.8						63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH		
	RT. STA. 1157+03.6-1158+02.2	98.4							JOHN DEERE ROAD			
	LT. STA. 1160+64.4-1163+50	265.6							RT. STA. 381+74.56-381+88.81		1	
	LT. STA. 1163+55-1172+28.24	873.2							52ND AVENUE			
	RT. STA. 1160+64.4-1164+73.7	417.3							LT. STA. 1157+07.46-1157+21.71		1	
	MEDIAN LT. STA. 1161+66.13-1165+15.69	348.3							RT. STA. 1161+85.83-1162+00.08		1	
	MEDIAN RT. STA. 1161+66.13-1165+15.69	349.6							TOTAL		3	
	RT. STA. 1164+73.7-1165+68.8 (W. RADIUS)	151.2							63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	
	RT. STA. 1166+46.9-1167+98 (E. RADIUS)	188.7								MILAN BELTWAY		
	RT. STA. 1167+98-218+00	1,393.6								LT. STA. 364+11.13-364+24.38		1
	MEDIAN LT. STA. 1172+80.81-214+49.20	529.9								RT. STA. 356+83.28-356+96.53		1
	MEDIAN RT. STA. 1172+80.81-214+49.20	537.7								JOHN DEERE ROAD		
	LT. STA. 1173+66.2-218+00	807.9								RT. STA. 381+36.31-381+49.56		1
										52ND AVENUE		
	VALLEY VIEW									LT. STA. 1157+96.71-1158+09.96		1
	NW RADIUS STA. 151+15-152+45	207.4								RT. STA. 1160+35.08-1160+48.33		1
	SE RADIUS STA. 151+63-154+00	230.3								TOTAL		5
	LT. STA. 152+46.9-154+00	163.2										
	RT. STA. 152+46.54-154+00	142.6										
	LT. STA. 159+99.77-160+09.77	10.0										
	TRINITY DRIVE											
	W. RADIUS LT. STA. 0+45-0+98.5	97.6										
	E. RADIUS RT. STA. 0+49-0+98.4	97.6										
	TOTAL	9,997.1										
60605400	COMBINATION CONCRETE CURB & GUTTER, TYPE M-6.24 (SPECIAL)	FT.				60618300	CONCRETE MEDIAN SURFACE, 4 INCH	S. F.				
	VALLEY VIEW						BLACKHAWK ROAD					
	RT. STA. 154+00-160+09.8	608.8					N. W. ISLAND LT. STA. 1151+80	75				
							MEDIAN STA. 1152+61.00-1156+63.48	4,687				
	TOTAL	608.8					N. W. ISLAND LT. STA. 1156+58	190				
							S. W. ISLAND RT. STA. 1156+24	1,032				
							52ND AVENUE					
							MEDIAN STA. 1161+66.12-1165+07.35	3,554				
							S. E. ISLAND RT. STA. 1166+93	148				
							N. W. ISLAND LT. STA. 1172+27	134				
							MEDIAN STA. 1172+91.64-214+35.08	5,800				
							44TH STREET					
							LT. STA. 15+53.2-19+56	414.0				
							RT. STA. 15+54.3-16+61.4	111.5				
							RT. STA. 17+92.6-19+69	288.0				
							S. E. ISLAND @ BLACKHAWK RD.	44.9				
							LT. STA. 17+18.70-17+43	36.0				
							TOTAL	1,192.9				
							60619100	CONCRETE MEDIAN, TYPE SB (SPECIAL)	S. F.			
								BLACKHAWK ROAD				
								LT. STA. 1148+44.00-1151+63.02	1,908.7			
								52ND AVENUE				
								RT. STA. 1157+57.52-1157+90.86	391.2			
								RT. STA. 1160+52.50-1161+66.12	979.3			
								RT. STA. 1166+44.97-LT. STA. 1171+96.23	2,829.8			
								TOTAL	6,109.0			
								60624600	CORRUGATED MEDIAN	S. F.		
									52ND AVENUE			
									RT. STA. 1165+15.69-1165+53.18	194.9		
									LT. STA. 213+89.96-215+70.33	678.5		
									TOTAL	873.4		
									60900140	TYPE B INLET BOX, STANDARD 609006	EACH	
										52ND AVENUE		
										LT. STA. 1157+93.5		1
										TOTAL		1