

F.A.P. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
840	(1392-1)I	KANKAKEE	24	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CONTRACT# 66131

MAINLINE							
LOCATION	BIT SURF	SUB GRAN	BIT BSE CSE	BIT MAT	LEVEL BIND	BIT CONC SURF CS	TEMP
	REM 1 1/2"	MAT, TY A, 4	SUPER, 9"	PRIME COAT	(MM), SUPER, N70	SUPER, MIX "C", N70	RAMP
	SQ YD	SQ YD	SQ YD	GALLON	TON	TON	SQ YD
STA. 456+80 TO STA. 457+0	63			5		6	32
STA. 457+00 TO STA. 458+00		323	311	25	13	26	
STA. 458+00 TO STA. 459+2	402			32		34	32
TOTALS	465	323	311	62	13	66	64

EARTHWORK SCHEDULE					
LOCATION		1	2	3	4
	REM & DISP OF UNSUITABLE MATERIAL	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTH WORK BALANCE (+) OR SHORTAGE (-)
	CU YD	CU YD	CU YD	CU YD	CU YD
STA. 456+80 TO STA. 458+00		7	5	78	-73
EXCAVATION FOR STRUCTURE & POR GRAN EMB		1068	1068	0	1068
UNDERCUTTING	380				
TOTAL	380	1075	1073	78	995

SF= SHRINKAGE FACTOR= 25%
COLUMN 2= COLUMN 1*(1-SF)
COLUMN 4= COLUMN 2-COLUMN 3

PAVEMENT MARKING			
LOCATION	THERMOPLASTIC		
	LETTERS & SYMBOLS	LINE 6"	LINE 24"
	WHITE SQ FT	WHITE FOOT	WHITE FOOT
STA. 456+80 TO 459+23			
CENTERLINE		60	
RAILROAD "R"	14.4		
RAILROAD "X"	108		
BARS			56
TOTALS	122.4	60	56

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: VERT. _____
HORIZ. _____

DATE _____

DRAWN BY _____
CHECKED BY _____