



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 6, 2016

SUBJECT: FAU 7359 (Mound Road)
Section 13-00325-00-BR (Decatur)
Macon County
Contract No. 95784
Item 137
April 22, 2016 Letting
Addendum (A)

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans and/or the proposal. This addendum involves revised, added and/or deleted material.

1. Revised page 5 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Maureen M. Addis, P.E.
Acting Bureau Chief of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E.".

By: Ted B. Walschleger, P.E.
Engineer of Project Management

S.N. 058-3037 on Mound Road. Temporary pavement marking, signs, temporary concrete barriers and temporary impact attenuators shall be installed in accordance with the Maintenance of Traffic Plans. Temporary concrete barrier and its relocation shall be paid for separately. Wet reflective pavement markings will be required for the temporary pavement marking.

Pavement marking, centerline skips and edge lines, and raised reflective pavement markers that conflict with the traffic control and temporary pavement marking shall be removed and shall not be measured for payment.

Traffic Control and Protection, Standard 701611 will be paid for at the contract unit price L SUM for TRAFFIC CONTROL AND PROTECTION, STANDARD 701611.

TRAFFIC CONTROL AND PROTECTION, STANDARD 701801

Traffic Control and Protection, Standard 701801 shall be utilized for sidewalk work and to close any sidewalks during construction.

Traffic Control and Protection, Standard 701801 shall be paid for at the L SUM contract unit price for TRAFFIC CONTROL AND PROTECTION, STANDARD 701801.

TRAFFIC CONTROL AND PROTECTION, STANDARD 701901

Traffic Control and Protection, Standard 701901 applies to traffic control devices to be used on this project. Traffic Control and Protection, Standard 701901 shall not be paid for separately, but shall be considered included in the cost of the contract.

WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH

This work shall include, in addition to the provisions according to Section 703 of the Standard Specifications, the removal of any temporary tape specified for the construction of this project.

This work shall be paid for at the contract unit foot price for WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH and no additional compensation will be allowed. Removal of the temporary tape shall not be measured for pavement.

COMPLETION DATE PLUS GUARANTEED WORKING DAYS

The Contractor shall complete all contract items and safely open all roadways to traffic by December 16th, 2016 except as specified herein.

The Contractor will be allowed to complete all clean-up work and punch list items within fifteen (15) guaranteed working days after the completion date for opening the roadway to traffic. Under extenuating circumstances the Engineer may direct that certain items of work, not affecting the safe opening of the roadway to traffic, may be completed within the guaranteed working days allowed for clean-up work and punch list items. Temporary lane closures for this work may be allowed at the discretion of the Engineer.