

SUMMARY OF QUANTITIES

1000  
100% STATE

CODE NO.	ITEM	UNIT	TOTAL
* 20100500	TREE REMOVAL, ACRES	ACRE	0.7
* 20200100	EARTH EXCAVATION	CU YD	2,958
20201450	SUB-BASE GRANULAR MATERIAL, TYPE A	CU YD	2,235
20400800	FURNISHED EXCAVATION	CU YD	5,503
* 20700300	POROUS GRANULAR EMBANKMENT, SPECIAL	TON	550
20800150	TRENCH BACKFILL	CU YD	75
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	769
25000100	SEEDING, CLASS 1	ACRE	1.4
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	126
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	126
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	126
25100115	MULCH, METHOD 2	ACRE	0.2
25100630	EROSION CONTROL BLANKET	SQ YD	5,200
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	840
28000400	PERIMETER EROSION BARRIER	FOOT	100
28000500	INLET AND PIPE PROTECTION	EACH	21
28100107	STONE RIPRAP, CLASS A4	SQ YD	55
28200200	FILTER FABRIC	SQ YD	55
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	10
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	8
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	625
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	415
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	20
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	420
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	610

\* SEE SPECIAL PROVISIONS

1000  
100% STATE

CODE NO.	ITEM	UNIT	TOTAL
* 44002500	GUTTER OUTLET REMOVAL	EACH	2
44004250	PAVED SHOULDER REMOVAL	SQ YD	105
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	105
* 50105220	PIPE CULVERT REMOVAL	FOOT	90
5421D018	PIPE CULVERTS, CLASS D, TYPE 1 18" (TEMPORARY)	FOOT	45
54213666	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 21"	EACH	1
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	60
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	90
550A0400	STORM SEWERS, CLASS A, TYPE 2 21"	FOOT	220
550A0640	STORM SEWERS, CLASS A, TYPE 3 12"	FOOT	75
550A0700	STORM SEWERS, CLASS A, TYPE 3 21"	FOOT	380
60218300	MANHOLES, TYPE A, 4' - DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	13
* 60228500	MANHOLES, SPECIAL WITH SPECIAL FRAME AND GRATE	EACH	2
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	3
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	3
60500060	REMOVING INLETS	EACH	1
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	1,580
63200310	GUARD RAIL REMOVAL	FOOT	800
67100100	MOBILIZATION	L SUM	1
* 70103700	TRAFFIC CONTROL COMPLETE	L SUM	1
☒ 78001110	PAINT PAVEMENT MARKING-LINE 4"	FOOT	540
* Z0013798	CONSTRUCTION LAYOUT	L SUM	1
* Z0028415	GEOTECHNICAL REINFORCEMENT	SQ YD	4,890
* X6060160	COMBINATION CONCRETE CURB AND GUTTER OUTLET, (SPECIAL)	EACH	2
* X6060165	CONCRETE CURB AND GUTTER OUTLET, (SPECIAL)	EACH	2

\* SEE SPECIAL PROVISIONS

☒ SPECIALTY ITEM

FILE NAME =	USER NAME = #USLR#	DESIGNED - PJM	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>		F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN - DVH	REVISED -		SCALE:	SHEET NO. 2 OF 24 SHEETS	STA.	NORTH SLOPE ROAD	CARROLL	24	2
PLOT SCALE = #SCALE#		CHECKED - RGD	REVISED -								
PLOT DATE = #DATE#		DATE - 12-21-09	REVISED -					FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT	<b>CONTRACT NO. 46030</b>