

CODE NUMBER	PAY ITEM	UNIT	Y002 - 1C 100% STATE TOTAL QUANTITY	URBAN ROCK ISLAND COUNTY	URBAN WINNEBAGO COUNTY
T9990710	REMOVE <sup>AND</sup> REINSTALL WALKWAY	FOOT	288.00	189.00	99.00
T9991300	REMOVE EXISTING SIGN PANEL	EACH	8.00	8.00	
T9992530	REPLACE <sup>AND</sup> TIGHTEN <sup>SIGN MOUNTING</sup> CLIPS PER SIGN	EACH	12.00	8.00	4.00
T9992700	REMOVE <sup>AND</sup> REINSTALL SIGN PANEL	SQ FT	1,989.00	1,374.00	615.00
X0325265	REMOVE ELECTRIC SERVICE	EACH	7.00	5.00	2.00
67100100	MOBILIZATION	L SUM	1.00	0.80	0.20
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1.00	0.80	0.20
72000300	SIGN PANEL - TYPE 3	SQ FT	920.00	920.00	
72100100	SIGN PANEL OVERLAY	SQ FT	3,072.00	2,456.00	616.00
73300100	OVERHEAD SIGN STRUCTURE-SPAN, TYPE I-A (4'-0" X 4'-6")	FOOT	87.00		87.00
73300200	OVERHEAD SIGN STRUCTURE-SPAN, TYPE II-A (4'-6" X 5'-3")	FOOT	418.00	310.00	108.00
73302170	OVERHEAD SIGN STRUCTURE-CANTILEVER, TYPE II-C-A (36" X 5'-6")	FOOT	60.00	60.00	
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	131.10	86.10	45.00
73600100	REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	5.00	3.00	2.00
73600200	REMOVE OVERHEAD SIGN STRUCTURE-CANTILEVER	EACH	2.00	2.00	
73700300	REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	16.00	10.00	6.00
73800100	STRUCTURAL STEEL SUPPORT FOR OVERHEAD SIGN STRUCTURE-SPAN	EACH	10.00	6.00	4.00
X0325702	NIGHTTIME WORK ZONE LIGHTING	L SUM	1.00	0.80	0.20

FILE NAME \*  
#FILES\*

USER NAME \* #USERS

DESIGNED -

REVISED -

PLOT SCALE \* #SCALES

DRAWN -

REVISED -

PLOT DATE \* #DATES

CHECKED -

REVISED -

DATE -

REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

Summary and Schedule of Quantities

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.  
RTE.

SECTION

COUNTY

TOTAL SHEETS

SHEET NO.

\* 10-2 DVD SIGN STR REPL 2010-36 \*

\* Rock Island & Winnebago CONTRACT NO. 4601 \*

\* Various ILLINOIS FED. AID PROJECT \*