

Location No.:	2-01	State I.D. No.:	2S101U020R020.7				
County:	Winnebago	Route:	US-20	M.P.:	20.7	Direction:	EB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00					
STRUCTURAL STEEL SUPPORT FOR OVERHEAD SIGN STRUCTURE	EACH	2.00					
OVERHEAD SIGN STRUCTURE-SPAN, TYPE II-A	FOOT	108.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	306.25					
REMOVE & REINSTALL WALKWAY	FOOT	53.00					
REPLACE / TIGHTEN CLIPS PER SIGN	EACH	2.00					
REMOVE ELECTRIC SERVICE	EACH	1.00					
SIGN PANEL OVERLAY	SQ FT	306.25					
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	24.30					
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	2.00					

Location No.:	2-02	State I.D. No.:	2S101U020R019.8				
County:	Winnebago	Route:	US-150	M.P.:	1.5	Direction:	WB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00					
STRUCTURAL STEEL SUPPORT FOR OVERHEAD SIGN STRUCTURE	EACH	2.00					
OVERHEAD SIGN STRUCTURE-SPAN, TYPE I-A	FOOT	87.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	309.25					
REMOVE & REINSTALL WALKWAY	FOOT	46.00					
SIGN PANEL OVERLAY	SQ FT	309.50					
REMOVE ELECTRIC SERVICE	EACH	1.00					
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	20.70					
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	4.00					
REPLACE / TIGHTEN CLIPS PER SIGN	EACH	2.00					

Location No.:	2-03	State I.D. No.:	2S081I074R003.4				
County:	Rock Island	Route:	I-74	M.P.:	3.4	Direction:	EB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00					
STRUCTURAL STEEL SUPPORT FOR OVERHEAD SIGN STRUCTURE	EACH	2.00					
OVERHEAD SIGN STRUCTURE-SPAN, TYPE II-A	FOOT	94.00					
REMOVE & RE-INSTALL SIGN PANEL	SQ FT	662.50					
REMOVE & REINSTALL WALKWAY	FOOT	60.00					
REPLACE / TIGHTEN CLIPS PER SIGN	EACH	3.00					
REMOVE ELECTRIC SERVICE	EACH	1.00					
SIGN PANEL OVERLAY	SQ FT	662.75					
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	22.00					
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	4.00					

Location No.:	2-04	State I.D. No.:	2C081I0JDL000.0				
County:	Rock Island	Route:	John Deere Rd	M.P.:	0	Direction:	WB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-CANTILEVER	EACH	1.00					
OVERHEAD SIGN STRUCTURE-CANTILEVER, TYPE II-C-A	FOOT	30.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	152.00					
REMOVE & REINSTALL WALKWAY	FOOT	20.00					
REMOVE ELECTRIC SERVICE	EACH	1.00					
SIGN PANEL OVERLAY	SQ FT	152.00					
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	8.80					
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	1.00					
REPLACE / TIGHTEN CLIPS PER SIGN	EACH	1.00					

Location No.:	2-05	State I.D. No.:	2C081I074R003.6				
County:	Rock Island	Route:	I-74	M.P.:	3.6	Direction:	EB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-CANTILEVER	EACH	1.00					
OVERHEAD SIGN STRUCTURE-CANTILEVER, TYPE II-C-A	FOOT	30.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	223.50					
REMOVE & REINSTALL WALKWAY	FOOT	23.00					
REPLACE / TIGHTEN CLIPS PER SIGN	EACH	1.00					
REMOVE ELECTRIC SERVICE	EACH	1.00					
SIGN PANEL OVERLAY	SQ FT	223.75					
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	8.80					
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	1.00					

Location No.:	2-06	State I.D. No.:	2S081I088R000.5				
County:	Rock Island	Route:	I-88	M.P.:	0.4	Direction:	EB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00					
OVERHEAD SIGN STRUCTURE-SPAN, TYPE II-A	FOOT	116.00					
STRUCTURAL STEEL SUPPORT FOR OVERHEAD SIGN STRUCTURE	EACH	2.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	155.00					
REMOVE & REINSTALL WALKWAY	FOOT	47.00					
REPLACE / TIGHTEN CLIPS PER SIGN	EACH	1.00					
REMOVE ELECTRIC SERVICE	EACH	1.00					
SIGN PANEL OVERLAY	SQ FT	155.00					
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	25.00					
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	2.00					
REMOVE EXISTING SIGN PANEL	EACH	1.00					
SIGN PANEL, TYPE 3	SQ FT	97.50					

Location No.:	2-07	State I.D. No.:	2S081I088L000.8				
County:	Rock Island	Route:	I-88	M.P.:	0.8	Direction:	WB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00					
STRUCTURAL STEEL SUPPORT FOR OVERHEAD SIGN STRUCTURE	EACH	2.00					
OVERHEAD SIGN STRUCTURE-SPAN, TYPE II-A	FOOT	100.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	180.50					
REMOVE & REINSTALL WALKWAY	FOOT	39.00					
REPLACE / TIGHTEN CLIPS PER SIGN	EACH	2.00					
REMOVE ELECTRIC SERVICE	EACH	1.00					
SIGN PANEL OVERLAY	SQ FT	180.50					
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	21.50					
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	2.00					
REMOVE EXISTING SIGN PANEL	EACH	1.00					
SIGN PANEL, TYPE 3	SQ FT	195.50					

Location No.:	2-08	State I.D. No.:	2S081I088L001.7				
County:	Rock Island	Route:	I-88	M.P.:	1.7	Direction:	WB
Description of Work	Unit	Quantity					
SIGN PANEL OVERLAY	SQ FT	225.00					
REMOVE EXISTING SIGN PANEL	EACH	1.00					
SIGN PANEL, TYPE 3	SQ FT	93.50					

Location No.:	2-09	State I.D. No.:	2S081I088L001.0				
County:	Rock Island	Route:	I-88	M.P.:	1	Direction:	WB
Description of Work	Unit	Quantity					
SIGN PANEL OVERLAY	SQ FT	193.75					
REMOVE EXISTING SIGN PANEL	EACH	2.00					
SIGN PANEL, TYPE 3	SQ FT	252.50					

Location No.:	2-10	State I.D. No.:	GROUND MOUNTED				
County:	Rock Island	Route:	I-88	M.P.:	1.35	Direction:	WB
Description of Work	Unit	Quantity					
REMOVE EXISTING SIGN PANEL	EACH	1.00					
SIGN PANEL, TYPE 3	SQ FT	93.50					

Location No.:	2-11	State I.D. No.:	2S081S005R Sta 217+00				
County:	Rock Island	Route:	IL - 5	M.P.:		Direction:	EB
Description of Work	Unit	Quantity					
SIGN PANEL OVERLAY	SQ FT	382.75					
REMOVE EXISTING SIGN PANEL	EACH	1.00					
SIGN PANEL, TYPE 3	SQ FT	93.50					

Location No.:	2-12	State I.D. No.:	2S081S005R Sta 232+00				
County:	Rock Island	Route:	IL - 5	M.P.:		Direction:	EB
Description of Work	Unit	Quantity					
SIGN PANEL OVERLAY	SQ FT	281.00					
REMOVE EXISTING SIGN PANEL	EACH	1.00					
SIGN PANEL, TYPE 3	SQ FT	93.50					

FILE NAME	USER NAME	DESIGNED	REVISED
#FILE#	#USER#	DRAWN	REVISED
		CHECKED	REVISED
		DATE	REVISED

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

*Schedule of Overhead
Sign Structure Replacement*

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
* I-2 OVD SIGN STR REPL 200-36		**	31	3
* Rock Island & Winnebago		CONTRACT NO.	46101	
* Various		(ILLINOIS) FED. AID PROJECT		