

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

Various Routes  
D 6 OVD SIN STR REPL 2010-38  
Pike & Sangamon Counties  
Sheet 4 of 27  
Contract Number 46103

District 6  
Schedule of Overhead Sign Structure Replacement

Location No.:	6-01	State I.D. No.:	6C084I055R099.7		
County:	Sangamon	Route:	I-55	M.P.:	99.7
				Direction:	NB
Description of Work	Unit	Quantity			
REMOVE OVERHEAD SIGN STRUCTURE-CANTILEVER	EACH	1.00			
OVERHEAD SIGN STRUCTURE-CANTILEVER, TYPE II-C-A	FOOT	30.00			
REMOVE & REINSTALL SIGN PANEL	SQ FT	198.00			
REMOVE & REINSTALL WALKWAY	FOOT	17.00			
REPLACE / TIGHTEN CLIPS PER SIGN	EACH	1.00			
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	4.00			
DISCONNECT/RECONNECT ELECTRIC SERVICE	EACH	1.00			
RELOCATE ELECTRIC SERVICE	EACH	1.00			
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	7.12			
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	1.00			
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00			
REMOVE & REINSTALL VIDEO CAMERA & EQUIPMENT	EACH	1.00			
This structure is being completely replaced.					
This work shall be completed during District 6 night time hours.					

Location No.:	6-02	State I.D. No.:	6C084I072R097.5		
County:	Sangamon	Route:	I-55	M.P.:	97.5
				Direction:	EB
Description of Work	Unit	Quantity			
REMOVE OVERHEAD SIGN STRUCTURE-CANTILEVER	EACH	1.00			
OVERHEAD SIGN STRUCTURE-CANTILEVER, TYPE II-C-A	FOOT	30.00			
REMOVE & REINSTALL SIGN PANEL	SQ FT	210.00			
REMOVE & REINSTALL WALKWAY	FOOT	20.00			
REPLACE / TIGHTEN CLIPS PER SIGN	EACH	1.00			
DISCONNECT/RECONNECT ELECTRIC SERVICE	EACH	1.00			
RELOCATE ELECTRIC SERVICE	EACH	1.00			
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	7.12			
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	1.00			
REMOVE AND REINSTALL VIDEO CAMERA & EQUIPMENT	EACH	1.00			
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00			
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	4.00			
This structure is being completely replaced.					
This work shall be completed during District 6 night time hours.					

Location No.:	6-08	State I.D. No.:	6S084I072R097.		
County:	Sangamon	Route:	I-72	M.P.:	97
				Direction:	EB
Description of Work	Unit	Quantity			
GUARDRAIL REMOVAL	FOOT	12.50			
STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	25.00			
TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1.00			

Location No.:	6-03	State I.D. No.:	6S084B055L000.71		
County:	Sangamon	Route:	Bus-55	M.P.:	0.71
				Direction:	SB
Description of Work	Unit	Quantity			
REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00			
OVERHEAD SIGN STRUCTURE-SPAN, TYPE II-A	FOOT	81.00			
STRUCTURAL STEEL SUPPORT FOR OVERHEAD SIGN STRUCTURE	EACH	2.00			
REMOVE & REINSTALL SIGN PANEL	SQ FT	371.00			
REMOVE & REINSTALL WALKWAY	FOOT	55.25			
REPLACE / TIGHTEN CLIPS PER SIGN	EACH	3.00			
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	12.00			
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	23.66			
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	2.00			
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00			
IMPACT ATTENUATOR REMOVAL	EACH	2.00			
IMPACT ATTENUATORS (NON-REDIRECTIVE) TEST LEVEL 2	EACH	2.00			
ATTENUATOR BASE	SQ YD	59.50			
This structure is being completely replaced.					
This work shall be completed during District 6 night time hours.					

Location No.:	6-04	State I.D. No.:	6S084I055L096.7		
County:	Sangamon	Route:	I-55	M.P.:	96.7
				Direction:	SB
Description of Work	Unit	Quantity			
REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00			
OVERHEAD SIGN STRUCTURE-SPAN, TYPE II-A	FOOT	108.00			
STRUCTURAL STEEL SUPPORT FOR OVERHEAD SIGN STRUCTURE	EACH	2.00			
REMOVE & REINSTALL SIGN PANEL	SQ FT	566.50			
REMOVE & REINSTALL WALKWAY	FOOT	55.50			
REPLACE / TIGHTEN CLIPS PER SIGN	EACH	3.00			
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	14.00			
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	27.53			
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	2.00			
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00			
GUARDRAIL REMOVAL	FOOT	12.50			
STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	25.00			
TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1.00			
This structure is being completely replaced.					
This work shall be completed during District 6 night time hours.					

Location No.:	6-05	State I.D. No.:	6S084I072L103.3		
County:	Sangamon	Route:	I-72	M.P.:	103.3
				Direction:	WB
Description of Work	Unit	Quantity			
REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00			
OVERHEAD SIGN STRUCTURE-SPAN, TYPE II-A	FOOT	89.00			
STRUCTURAL STEEL SUPPORT FOR OVERHEAD SIGN STRUCTURE	EACH	2.00			
REMOVE & REINSTALL SIGN PANEL	SQ FT	553.00			
REMOVE & REINSTALL WALKWAY	FOOT	56.00			
REPLACE / TIGHTEN CLIPS PER SIGN	EACH	3.00			
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	12.00			
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	23.66			
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	4.00			
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00			
IMPACT ATTENUATOR REMOVAL	EACH	2.00			
IMPACT ATTENUATORS (NON-REDIRECTIVE) TEST LEVEL 3	EACH	2.00			
ATTENUATOR BASE	SQ YD	108.40			
This structure is being completely replaced.					
This work shall be completed during District 6 night time hours.					

Location No.:	6-06	State I.D. No.:	6S084I055L092.6		
County:	Sangamon	Route:	I-55	M.P.:	92.6
				Direction:	SB
Description of Work	Unit	Quantity			
REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00			
OVERHEAD SIGN STRUCTURE-SPAN, TYPE II-A	FOOT	122.00			
STRUCTURAL STEEL SUPPORT FOR OVERHEAD SIGN STRUCTURE	EACH	2.00			
REMOVE & REINSTALL SIGN PANEL	SQ FT	511.00			
REMOVE & REINSTALL WALKWAY	FOOT	76.00			
REPLACE / TIGHTEN CLIPS PER SIGN	EACH	2.00			
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	18.00			
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	25.12			
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	4.00			
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00			
This structure is being completely replaced.					
This work shall be completed during District 6 night time hours.					

Location No.:	6-07	State I.D. No.:	6S075I072L005.9		
County:	Pike	Route:	I-72	M.P.:	5.9
				Direction:	WB
Description of Work	Unit	Quantity			
REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00			
OVERHEAD SIGN STRUCTURE-SPAN, TYPE II-A	FOOT	79.00			
REMOVE & REINSTALL SIGN PANEL	SQ FT	319.00			
REMOVE & REINSTALL WALKWAY	FOOT	34.33			
REPLACE / TIGHTEN CLIPS PER SIGN	EACH	2.00			
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	9.00			
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00			
Only the sign truss is being replaced.					
This work shall be completed during District 6 day time hours.					