

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEM	UNIT	Y002 - 1C 100% STATE TOTAL QUANTITY	URBAN	RURAL
67100100	MOBILIZATION	L SUM	1.00		1.00
70100309	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	EACH	9.00		9.00
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	17.00		17.00
72000300	SIGN PANEL - TYPE 3	SQFT	2769.00		2769.00
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	2584.00		2584.00
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	10932.00		10932.00
73300200	OVERHEAD SIGN STRUCTURE - SPAN, TYPE II-A (4'-6" X 5'-3")	FOOT	190.00		190.00
73300300	OVERHEAD SIGN STRUCTURE - SPAN, TYPE III-A (5'-0" X 7'-0")	FOOT	130.00		130.00
73302170	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE II-C-A (36" X 5'-6")	FOOT	75.00		75.00
73400100	CONCRETE FOUNDATIONS	CUYD	27.30		27.30
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CUYD	27.00		27.00
73800100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	3.00		3.00
73800200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	16.00		16.00
73700300	REMOVE CONCRETE FOUNDATION OVERHEAD	EACH	16.00		16.00
73800100	STRUCTURAL STEEL SUPPORT FOR OVERHEAD SIGN STRUCTURE - SPAN	EACH	6.00		6.00
81603035	UNIT DUCT, 600V, 2-1C NO.6, 1/C NO.6 ^{GROUND} (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	135.00		135.00
T9996300	OVERHEAD SIGN SUPPORT GROUT REPAIR	EACH	12.00		12.00
X7012615	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	EACH	2.00		2.00
X7012630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	EACH	9.00		9.00
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	64.00		64.00
X7330105	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	288.00		288.00
X7330110	OVERHEAD SIGN STRUCTURE WALKWAY, CANTILEVER, TYPE A	FOOT	60.00		60.00
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	20.00		20.00
Z0002005	ATTENUATOR BASE	SQYD	35.00		35.00
Z0028999	IMPACT ATTENUATOR REMOVAL	EACH	6.00		6.00
Z0030150	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1.00		1.00

FILE NAME =	USER NAME = oreigre	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ct:\p\work\p\dot\oreigre\d0180151\05461	2-shht-500.dgn	DRAWN -	REVISED -			D-5 OSS REPL 2010-46	Various	77	2		
PLOT SCALE = 48.0000' / IN.	CHECKED -	REVISED -	REVISED -			Various	CONTRACT NO. 46110				
PLOT DATE = 2/4/2018	DATE -	REVISED -	REVISED -			ILLINOIS FED. AID PROJECT					
						SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.