

SCHEDULE OF QUANTITIES

CODE NUMBER	PAY ITEM	UNIT	Y002 - 1C 100% STATE TOTAL QUANTITY	OSSR-A	OSSR-B	OSSR-C	OSSR-D	OSSR-E	OSSR-F	SR-1	GM-1	GM-2	GM-3	GM-4	GM-5	GM-6	GM-7	GM-8	GM-9	GM-10	GM-11	GM-12	GM-13	
				5S057 S009 R019.00	5S057 S009 R019.10	5S057 S009 R019.40	5C092 S001 L027.29	5C092 S001 R027.13	5C092 S001 L027.09	5C092 S001 R026.99	5C092 S001 L027.48	5C092 S001 L027.44	5C092 S001 R027.25	5C092 S001 R027.23	5C092 S001 R027.03	5C092 I074 R209.90	5C092 I074 L213.80	5C092 I074 R213.70	5C092 I074 L213.79	5C010 I074 R000.05	5C010 I074 R000.13	5C010 I074 R000.19	5C010 I074 L000.29	
				MCLEAN CO. - ILLINOIS 9				VERMILION COUNTY - ILLINOIS RT 1 - TILTON and I-74 @ US 150 / Exit 210 and I-74 @ G Street / Exit 214										CHAMPAIGN CO. - NEIL ST. over I-74						
67100100	MOBILIZATION	L SUM	1.00	0.05	0.05	0.05	0.05	0.05	0.05	0.05	0.05	0.05	0.05	0.05	0.05	0.05	0.05	0.05	0.05	0.05	0.05	0.05	0.05	0.05
70100309	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	EACH	9.00	-	-	-	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	-	-	-	-	-	-	-	-	-
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	17.00	-	-	-	2.00	2.00	2.00	1.00	1.00	1.00	2.00	2.00	1.00	1.00	-	-	-	2.00	-	-	-	-
72000300	SIGN PANEL - TYPE 3	SQFT	2788.25	284.50	397.25	458.50	84.00	84.00	75.00	75.00	27.00	140.00	93.75	50.00	105.00	214.50	68.75	74.25	114.00	154.00	79.75	60.50	148.50	
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	2583.50	329.50	428.75	472.75	91.00	87.50	80.50	80.50	27.00	84.00	61.75	32.00	68.25	121.50	71.25	78.75	73.00	135.25	71.50	55.00	133.75	
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	10931.50	-	-	-	-	-	-	-	375.00	1209.00	813.00	525.00	813.00	1624.50	457.50	457.50	957.00	1105.00	657.00	555.00	1183.00	
73300200	OVERHEAD SIGN STRUCTURE - SPAN, TYPE II-A (4'-6" X 5'-3")	FOOT	190.00	80.00	-	110.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
73300300	OVERHEAD SIGN STRUCTURE - SPAN, TYPE III-A (5'-0" X 7'-0")	FOOT	130.00	-	130.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
73302170	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE II-C-A (36" X 5'-6")	FOOT	75.00	-	-	-	24.00	25.00	26.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
73400100	CONCRETE FOUNDATIONS	CUYD	27.28	-	-	-	-	-	-	-	1.40	2.54	2.36	1.40	2.36	4.18	1.40	1.40	2.36	2.54	1.40	1.40	2.54	
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CUYD	27.00	-	-	-	9.00	9.00	9.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	3.00	1.00	1.00	1.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	16.00	-	-	-	1.00	1.00	1.00	-	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	
73700300	REMOVE CONCRETE FOUNDATION OVERHEAD	EACH	16.00	-	-	-	1.00	1.00	1.00	-	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	
73800100	STRUCTURAL STEEL SUPPORT FOR OVERHEAD SIGN STRUCTURE - SPAN	EACH	6.00	2.00	2.00	2.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
81603035	UNIT DUCT, 600V, 2-1C NO.6, 1/C NO.6 GRND, (XLP-TYPE USE), 1" DIA. POLY	FOOT	135.00	-	-	-	-	-	-	-	-	-	-	-	135.00	-	-	-	-	-	-	-	-	
T9996300	OVERHEAD SIGN SUPPORT GROUT REPAIR	EACH	12.00	4.00	4.00	4.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
X7012615	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	EACH	2.00	-	-	-	-	-	-	-	-	-	-	-	-	1.00	-	-	-	1.00	-	-	-	
X7012630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	EACH	9.00	1.00	1.00	1.00	-	-	-	-	-	-	-	-	-	-	1.00	1.00	-	1.00	1.00	1.00	1.00	
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	64.00	-	-	-	7.00	4.00	4.00	1.00	4.00	4.00	4.00	4.00	4.00	14.00	-	-	-	14.00	-	-	-	
X7330105	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	288.00	60.00	106.00	102.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
X7330110	OVERHEAD SIGN STRUCTURE WALKWAY, CANTILEVER, TYPE A	FOOT	80.00	-	-	-	20.00	20.00	20.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	20.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	
Z0002005	ATTENUATOR BASE	SQYD	35.00	-	-	-	35.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
Z0028999	IMPACT ATTENUATOR REMOVAL	EACH	6.00	-	-	-	1.00	-	-	-	1.00	1.00	1.00	1.00	1.00	-	-	-	-	-	-	-	-	
Z0030150	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1.00	-	-	-	1.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	

OSSR = Overhead Sign Structure Replacement
 SR = Sign Replacement
 GM = Ground Mount