

**MCLEAN COUNTY SIGN STRUCTURES
ILLINOIS 9 @ LOOP 55 /VETERANS PARKWAY**

Location No.	OSSR-A		
Structure No.	5 S 057 S009 R019.00		
County / Route	MCLEAN CO. - ILLINOIS 9 - just west of Bus. Loop I-55		
Scope of Work	This overhead sign structure is being replaced on existing foundations.		
CODE NUMBER	PAY ITEM	UNIT	QUANTITY
72000300	SIGN PANEL - TYPE 3	SQFT	264.50
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	329.50
73300200	OVERHEAD SIGN STRUCTURE - SPAN, TYPE II-A (4'-6" X 5'-3")	FOOT	80.00
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	1.00
73800100	STRUCTURAL STEEL SUPPORT FOR OVERHEAD SIGN STRUCTURE - SPAN	EACH	2.00
T9996300	OVERHEAD SIGN SUPPORT GROUT REPAIR	EACH	4.00
X7012630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	EACH	1.00
X7330105	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	60.00
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	1.00

Location No.	OSSR-C		
Structure No.	5 S 057 S009 R019.40		
County / Route	MCLEAN CO. - ILLINOIS 9 - just west of Bus. Loop I-55		
Scope of Work	This overhead sign structure is being replaced on existing foundations.		
CODE NUMBER	PAY ITEM	UNIT	QUANTITY
72000300	SIGN PANEL - TYPE 3	SQFT	458.50
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	472.75
73300200	OVERHEAD SIGN STRUCTURE - SPAN, TYPE II-A (4'-6" X 5'-3")	FOOT	110.00
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	1.00
73800100	STRUCTURAL STEEL SUPPORT FOR OVERHEAD SIGN STRUCTURE - SPAN	EACH	2.00
T9996300	OVERHEAD SIGN SUPPORT GROUT REPAIR	EACH	4.00
X7012630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	EACH	1.00
X7330105	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	102.00
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	1.00

Location No.	OSSR-B		
Structure No.	5 S 057 S009 R019.10		
County / Route	MCLEAN CO. - ILLINOIS 9 - just west of Bus. Loop I-55		
Scope of Work	This overhead sign structure is being replaced on existing foundations.		
CODE NUMBER	PAY ITEM	UNIT	QUANTITY
72000300	SIGN PANEL - TYPE 3	SQFT	397.25
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	428.75
73300300	OVERHEAD SIGN STRUCTURE - SPAN, TYPE III-A (5'-0" X 7'-0")	FOOT	130.00
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	1.00
73800100	STRUCTURAL STEEL SUPPORT FOR OVERHEAD SIGN STRUCTURE - SPAN	EACH	2.00
T9996300	OVERHEAD SIGN SUPPORT GROUT REPAIR	EACH	4.00
X7012630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	EACH	1.00
X7330105	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	106.00
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	1.00