

**VERMILION COUNTY SIGN STRUCTURES
ILLINOIS 1 - TILTON**

Location No.	GM-1		
Structure No.	5 C 092 S001 L027.48		
County / Route	VERMILION CO. - ILLINOIS 1 NB - Tilton - just south of 14th St.		
Scope of Work	This overhead cantilever is to be removed & replaced with a breakaway ground mount.		
CODE NUMBER	PAY ITEM	UNIT	QUANTITY
70100309	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	EACH	1.00
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1.00
72000300	SIGN PANEL - TYPE 3	SQFT	27.00
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	27.00
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	375.00
73400100	CONCRETE FOUNDATIONS	CUYD	1.40
73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	1.00
73700300	REMOVE CONCRETE FOUNDATION OVERHEAD	EACH	1.00
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	4.00
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	1.00
Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	1.00

Location No.	OSSR-D		
Structure No.	5 C 092 S001 L027.29		
County / Route	VERMILION CO. - ILLINOIS 1 NB - Tilton - between 14th St. & I-74		
Scope of Work	This overhead cantilever is being replaced on a new foundation.		
CODE NUMBER	PAY ITEM	UNIT	QUANTITY
70100309	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	EACH	1.00
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	2.00
72000300	SIGN PANEL - TYPE 3	SQFT	84.00
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	91.00
73302170	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE II-C-A (36" X 5'-6")	FOOT	24.00
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CUYD	9.00
73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	1.00
73700300	REMOVE CONCRETE FOUNDATION OVERHEAD	EACH	1.00
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	7.00
X7330110	OVERHEAD SIGN STRUCTURE WALKWAY, CANTILEVER, TYPE A	FOOT	20.00
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	1.00
Z0002005	ATTENUATOR BASE	SQYD	35.00
Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	1.00
Z0030150	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1.00

Location No.	GM-2		
Structure No.	5 C 092 S001 L027.44		
County / Route	VERMILION CO. - ILLINOIS 1 NB - Tilton - just south of 14th St.		
Scope of Work	This overhead cantilever is to be removed & replaced with a breakaway ground mount.		
CODE NUMBER	PAY ITEM	UNIT	QUANTITY
70100309	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	EACH	1.00
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1.00
72000300	SIGN PANEL - TYPE 3	SQFT	140.00
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	84.00
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	1209.00
73400100	CONCRETE FOUNDATIONS	CUYD	2.54
73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	1.00
73700300	REMOVE CONCRETE FOUNDATION OVERHEAD	EACH	1.00
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	4.00
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	1.00
Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	1.00

Location No.	GM-3		
Structure No.	5 C 092 S001 L027.25		
County / Route	VERMILION CO. - ILLINOIS 1 NB - Tilton - between 14th St. & I-74		
Scope of Work	This overhead cantilever is to be removed & replaced with a breakaway ground mount.		
CODE NUMBER	PAY ITEM	UNIT	QUANTITY
70100309	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	EACH	1.00
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	2.00
72000300	SIGN PANEL - TYPE 3	SQFT	93.75
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	61.75
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	913.00
73400100	CONCRETE FOUNDATIONS	CUYD	2.36
73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	1.00
73700300	REMOVE CONCRETE FOUNDATION OVERHEAD	EACH	1.00
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	4.00
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	1.00
Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	1.00