

**VERMILION COUNTY SIGN STRUCTURES
ILLINOIS 1 - TILTON**

Location No.	GM-4		
Structure No.	5 C 092 S001 R027.23		
County / Route	VERMILION CO. - ILLINOIS 1 SB - Tilton - between 14th St. & I-74		
Scope of Work	This overhead cantilever is to be removed & replaced with a breakaway ground mount.		
CODE NUMBER	PAY ITEM	UNIT	QUANTITY
70100309	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	EACH	1.00
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	2.00
72000300	SIGN PANEL - TYPE 3	SQFT	50.00
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	32.00
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	525.00
73400100	CONCRETE FOUNDATIONS	CUYD	1.40
73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	1.00
73700300	REMOVE CONCRETE FOUNDATION OVERHEAD	EACH	1.00
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	4.00
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	1.00
Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	1.00

Location No.	OSSR-E		
Structure No.	5 C 092 S001 R027.13		
County / Route	VERMILION CO. - ILLINOIS 1 SB - Tilton - just south of I-74		
Scope of Work	This overhead cantilever is being replaced on a new foundation.		
CODE NUMBER	PAY ITEM	UNIT	QUANTITY
70100309	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	EACH	1.00
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	2.00
72000300	SIGN PANEL - TYPE 3	SQFT	84.00
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	87.50
73302170	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE II-C-A (36" X 5'-6")	FOOT	25.00
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CUYD	9.00
73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	1.00
73700300	REMOVE CONCRETE FOUNDATION OVERHEAD	EACH	1.00
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	4.00
X7330110	OVERHEAD SIGN STRUCTURE WALKWAY, CANTILEVER, TYPE A	FOOT	20.00
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	1.00

Location No.	OSSR-F		
Structure No.	5 C 092 S001 L027.09		
County / Route	VERMILION CO. - ILLINOIS 1 NB - Tilton - just north of I-74		
Scope of Work	This overhead cantilever is being replaced on a new foundation.		
CODE NUMBER	PAY ITEM	UNIT	QUANTITY
70100309	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	EACH	1.00
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	2.00
72000300	SIGN PANEL - TYPE 3	SQFT	75.00
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	80.50
73302170	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE II-C-A (36" X 5'-6")	FOOT	26.00
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CUYD	9.00
73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	1.00
73700300	REMOVE CONCRETE FOUNDATION OVERHEAD	EACH	1.00
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	4.00
X7330110	OVERHEAD SIGN STRUCTURE WALKWAY, CANTILEVER, TYPE A	FOOT	20.00
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	1.00

Location No.	GM-5		
Structure No.	5 C 092 S001 R027.03		
County / Route	VERMILION CO. - ILLINOIS 1 SB - Tilton - just north of & I-74		
Scope of Work	This overhead cantilever is to be removed & replaced with a breakaway ground mount.		
CODE NUMBER	PAY ITEM	UNIT	QUANTITY
70100309	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	EACH	1.00
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1.00
72000300	SIGN PANEL - TYPE 3	SQFT	105.00
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	68.25
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	913.00
73400100	CONCRETE FOUNDATIONS	CUYD	2.36
73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	1.00
73700300	REMOVE CONCRETE FOUNDATION OVERHEAD	EACH	1.00
81603035	UNIT DUCT, 600V, 2-1C NO.6, 1/C NO.6 GRND, (XLP-TYPE USE), 1" DIA. POLY	FOOT	135.00
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	4.00
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	1.00
Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	1.00

Location No.	SR-1		
Structure No.	5 C 092 S001 R026.99		
County / Route	VERMILION CO. - ILLINOIS 1 SB - Tilton - north of I-74		
Scope of Work	Replace green sign & remove electrical. Cantilever structure to remain in place.		
CODE NUMBER	PAY ITEM	UNIT	QUANTITY
70100309	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	EACH	1.00
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1.00
72000300	SIGN PANEL - TYPE 3	SQFT	75.00
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	80.50
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	1.00
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	1.00