

**VERMILION COUNTY SIGN STRUCTURES**  
**I-74 @ US 150 /EXIT 210 & G STREET /EXIT 214**

Location No.	GM-6		
Structure No.	5 C 092 I074 R209.90		
County / Route	VERMILION CO. - I-74 EB - Exit 210 - US 150/MLK		
Scope of Work	This overhead cantilever is to be removed & replaced with a breakaway ground mount.		
CODE NUMBER	PAY ITEM	UNIT	QUANTITY
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1.00
72000300	SIGN PANEL - TYPE 3	SQFT	214.50
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	121.50
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	1624.50
73400100	CONCRETE FOUNDATIONS	CUYD	4.18
73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	1.00
73700300	REMOVE CONCRETE FOUNDATION OVERHEAD	EACH	1.00
X7012615	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	EACH	1.00
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	14.00
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	1.00

Location No.	GM-8		
Structure No.	5 C 092 I074 R213.70		
County / Route	VERMILION CO. - intersection of G St. & 2nd St. - below I-74 EB - Exit 214		
Scope of Work	This overhead cantilever is to be removed & replaced with a breakaway ground mount.		
CODE NUMBER	PAY ITEM	UNIT	QUANTITY
72000300	SIGN PANEL - TYPE 3	SQFT	74.25
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	78.75
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	457.50
73400100	CONCRETE FOUNDATIONS	CUYD	1.40
73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	1.00
73700300	REMOVE CONCRETE FOUNDATION OVERHEAD	EACH	1.00
X7012630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	EACH	1.00
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	1.00

Location No.	GM-7		
Structure No.	5 C 092 I074 L213.60		
County / Route	VERMILION CO. - intersection of G St. & 1st St. - below I-74 WB - Exit 214		
Scope of Work	This overhead cantilever is to be removed & replaced with a breakaway ground mount.		
CODE NUMBER	PAY ITEM	UNIT	QUANTITY
72000300	SIGN PANEL - TYPE 3	SQFT	68.75
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	71.25
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	457.50
73400100	CONCRETE FOUNDATIONS	CUYD	1.40
73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	1.00
73700300	REMOVE CONCRETE FOUNDATION OVERHEAD	EACH	1.00
X7012630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	EACH	1.00
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	1.00

Location No.	GM-9		
Structure No.	5 C 092 I074 L213.79		
County / Route	VERMILION CO. - I-74 WB Mainline - Exit 214 - G Street		
Scope of Work	This overhead cantilever is to be removed & replaced with a breakaway ground mount.		
CODE NUMBER	PAY ITEM	UNIT	QUANTITY
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	2.00
72000300	SIGN PANEL - TYPE 3	SQFT	114.00
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	73.00
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	957.00
73400100	CONCRETE FOUNDATIONS	CUYD	2.36
73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	1.00
73700300	REMOVE CONCRETE FOUNDATION OVERHEAD	EACH	1.00
X7012615	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	EACH	1.00
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	14.00
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	1.00