

**CHAMPAIGN COUNTY SIGN STRUCTURES
NEIL STREET OVER I-74**

Location No.	GM-10		
Structure No.	5 C 010 I074 R000.05		
County / Route	CHAMPAIGN CO. - SB Neil St. in Champaign - between Anthony Dr. & I-74		
Scope of Work	This overhead cantilever is to be removed & replaced with a breakaway ground mount.		
CODE NUMBER	PAY ITEM	UNIT	QUANTITY
72000300	SIGN PANEL - TYPE 3	SQFT	154.00
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	135.25
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	1105.00
73400100	CONCRETE FOUNDATIONS	CUYD	2.54
73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	1.00
73700300	REMOVE CONCRETE FOUNDATION OVERHEAD	EACH	1.00
X7012630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	EACH	1.00
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	1.00

Location No.	GM-12		
Structure No.	5 C 010 I074 R000.19		
County / Route	CHAMPAIGN CO. - SB Neil St. in Champaign - between I-74 & Kenyon Rd.		
Scope of Work	This overhead cantilever is to be removed & replaced with a breakaway ground mount.		
CODE NUMBER	PAY ITEM	UNIT	QUANTITY
72000300	SIGN PANEL - TYPE 3	SQFT	60.50
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	55.00
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	555.00
73400100	CONCRETE FOUNDATIONS	CUYD	1.40
73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	1.00
73700300	REMOVE CONCRETE FOUNDATION OVERHEAD	EACH	1.00
X7012630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	EACH	1.00
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	1.00

Location No.	GM-11		
Structure No.	5 C 010 I074 R000.13		
County / Route	CHAMPAIGN CO. - NB Neil St. in Champaign - between I-74 & Anthony Dr.		
Scope of Work	This overhead cantilever is to be removed & replaced with a breakaway ground mount.		
CODE NUMBER	PAY ITEM	UNIT	QUANTITY
72000300	SIGN PANEL - TYPE 3	SQFT	79.75
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	71.50
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	657.00
73400100	CONCRETE FOUNDATIONS	CUYD	1.40
73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	1.00
73700300	REMOVE CONCRETE FOUNDATION OVERHEAD	EACH	1.00
X7012630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	EACH	1.00
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	1.00

Location No.	GM-13		
Structure No.	5 C 010 I074 L000.29		
County / Route	CHAMPAIGN CO. - NB Neil St. in Champaign - between Kenyon Rd. & I-74		
Scope of Work	This overhead cantilever is to be removed & replaced with a breakaway ground mount.		
CODE NUMBER	PAY ITEM	UNIT	QUANTITY
72000300	SIGN PANEL - TYPE 3	SQFT	148.50
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	133.75
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	1183.00
73400100	CONCRETE FOUNDATIONS	CUYD	2.54
73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	1.00
73700300	REMOVE CONCRETE FOUNDATION OVERHEAD	EACH	1.00
X7012630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	EACH	1.00
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	1.00