

SUMMARY OF QUANTITIES				100%	CONSTRUCT
CODE NO.	ITEM DESCRIPTION	UNIT	STATE TOTAL	I000-2A	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	41	41	
<del>21101015</del>	<del>TOPSOIL FURNISH IN PLACE, 4"</del>	<del>SQ YD</del>	<del>320</del>	<del>320</del>	
40600300	AGGREGATE (PRIME COAT)	TON	204	204	
<del>25200110</del>	<del>SODDING, SALT TOLERANT</del>	<del>SQ YD</del>	<del>320</del>	<del>320</del>	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	103	103	
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL 4.75, N50	TON	2,880	2,880	
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1,552	1,552	
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	921	921	
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	6,720	6,720	
42001300	PROTECTIVE COAT	SQ YD	68	68	
<del>44000200</del>	<del>DRIVEWAY PAVEMENT REMOVAL</del>	<del>SQ YD</del>	<del>200</del>	<del>200</del>	
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	67,859	67,859	
<del>42300400</del>	<del>PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH</del>	<del>SQ YD</del>	<del>200</del>	<del>200</del>	
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1,400	1,400	
<del>44003510</del>	<del>MEDIAN REMOVAL, PARTIAL DEPTH</del>	<del>SQ FT</del>	<del>5,973</del>	<del>5,973</del>	
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	4,639	4,639	
<del>44004610</del>	<del>SIDEWALK REMOVAL AND REPLACEMENT (SPECIAL)</del>	<del>SQ FT</del>	<del>500</del>	<del>500</del>	
<del>44201761</del>	<del>CLASS D PATCHES, TYPE I, 10 INCH</del>	<del>SQ YD</del>	<del>450</del>	<del>450</del>	
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	700	700	
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	650	650	
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	2,761	2,761	
55039700	STORM SEWERS TO BE CLEANED	FOOT	500	500	
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	90	90	
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	125	125	
<del>60406100</del>	<del>FRAMES AND LIDS, TYPE I, CLOSED LID</del>	<del>EACH</del>	<del>12</del>	<del>12</del>	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1,836	1,836	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	570	570	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	10,747	10,747	

SUMMARY OF QUANTITIES				100%	CONSTRUCT
CODE NO.	ITEM DESCRIPTION	UNIT	STATE TOTAL	I000-2A	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	4,711	4,711	
<del>70300260</del>	<del>TEMPORARY PAVEMENT MARKING - LINE 12"</del>	<del>FOOT</del>	<del>920</del>	<del>920</del>	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	745	745	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	612	612	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	570	570	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	18,747	18,747	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	4,711	4,711	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	920	920	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	745	745	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	750	750	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	750	750	
<del>81400115</del>	<del>HANDHOLE TO BE ADJUSTED</del>	<del>EACH</del>	<del>4</del>	<del>4</del>	
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	2,105	2,105	
X0322256	TEMPORARY INFORMATIONAL SIGNING	SQ FT	205	205	
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	30	30	
Z0018600	DRAINAGE STRUCTURES TO BE RECONSTRUCTED	EACH	10	10	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	EACH	1	1	

\* SPECIALTY ITEM

FILE NAME =	USER NAME = \$USER\$	DESIGNED - KSD	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#	PLOT SCALE = \$SCALE\$	DRAWN - AZM	REVISED -					1376	(136,464EXT&0506) RS-6	COOK	27	3
	PLOT DATE = \$DATE\$	CHECKED - CMJ	REVISED -		SCALE: NTS	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	CONTRACT NO. 60F67			
		DATE - 01/13/10	REVISED -		ILLINOIS FED. AID PROJECT							

Rev.