

SCHEDULE OF QUANTITIES

STATION		SIGN PANEL ASSEMBLY REMOVAL (EACH)	SIGN ID #	SIZE (inches)	SIGN PANEL TYPE 1 (SQ.FT.)	TELESCOPING STEEL SIGN SUPPORT (FT.)	WOOD POST (FT.)	COMMENTS
340+77	RT	1	W1-2	30x30	6.25	14.5		
343+88	RT	1	W2-1	30x30	6.25		17	
			W16-8	30x8	1.67			
345+79	RT	1	W1-8L	12x18	1.5	12.5		
			W1-8R	12x18	1.5	12.5		
346+80	RT	1	W1-8L	12x18	1.5	12.5		
			W1-8R	12x18	1.5	12.5		
347+99	RT	1	W1-8L	12x18	1.5	12.5		
			W1-8R	12x18	1.5	12.5		
349+50	RT	1	R1-1	36x36	9	14		
349+58	RT	1	W1-8L	12x18	1.5	12.5		
			W1-8R	12x18	1.5	12.5		
350+55	RT	1	W1-8L	12x18	1.5	12.5		
			W1-8R	12x18	1.5	12.5		
351+58	RT	1	W1-8L	12x18	1.5	12.5		
			W1-8R	12x18	1.5	12.5		
352+64	RT	1	R2-1	24x30	5	12.5		
353+32	RT	1	W11	30x30	6.25	14.5		
364+30	RT	1	R2-1	24x30	5	13.5		
374+06	RT	1	W14-3	36x48x48	5.5	26		
			W2-2	30x30	6.25	28		
377+29	RT	1	W16-8	30x8	1.67			
			R1-1	30x30	6.25	28		
384+20	RT	1	OM-3R	12x36	3	13.5		
384+47	RT	1	OM-3R	12x36	3	13.5		
386+86	RT	1	R2-1	24x30	5	12.5		
390+65	RT	1	W6-1	36x36	9	15.5		
403+16	RT	1	W11-10	30x30	6.25	15		
409+28	RT	1	W4-3	36x36	9	15.5		
413+23	RT	1	W6-2	36x36	9	15.5		
414+81	RT	1	R2-1	24x30	5	13.5		
417+53	RT	1	W2-3	30x30	6.25	30		
			W16-8	30x8	1.67			
422+77	RT	1	R8	18x24	3			
			W4-2R	30x30	6.25	15		

STATION		SIGN PANEL ASSEMBLY REMOVAL (EACH)	SIGN ID #	SIZE (inches)	SIGN PANEL TYPE 1 (SQ.FT.)	TELESCOPING STEEL SIGN SUPPORT (FT.)	WOOD POST (FT.)	COMMENTS
424+11	RT	1	R3-2	24x24	4			
			R3-2	24x24	4	13		
424+32	RT	1	W1-7	48x24	8	26		
426+19	RT	1	W1-8L	12x18	1.5	12.5		REMOVE SIGNS ON RIGHT
427+15	RT	1	W1-8L	12x18	1.5	12.5		INSTALL SIGNS ON LEFT
428+10	RT	1	W1-8L	12x18	1.5	12.5		
429+71	RT	1	R2-1	24x30	5	13.5		
433+54	RT	1	W1-2	30x30	6.25	14.5		
			W2-3	30x30	6.25	26		
443+03	RT	1	W16-8	30x8	1.67			
			R1-1	36X36	9	28		
447+50	RT	1	R1-1	36X36	9	28		
456+86	RT	1	W2-3	30x30	6.25	26		
			W16-8	30x8	1.67			
465+50	RT	1	R1-1	36X36	9	28		
519+61	RT	1	S4-I105	24x24	4			
			W14-3	36x48x48	5.5	26		
522+43	RT	1	W1-2	30x30	6.25	16		
			W13-1	18x18	2.25			
525+97	RT	1	W2-1	30x30	6.25	26		
			W16-8	30x8	1.67			
532+25	RT	1	R3-8	30x30	6.25	13		
536+75	RT	1	R1-1	30x30	6.25	32		
			W4-4p	24x12	2			
570+85	RT	1	W14-3	36x48x48	5.5	26		
611+63	RT	1	W1-2	30x30	6.25	16.5		
			W13-1	18x18	2.25			
615+84	RT	1	W1-10R	30x30	6.25	26		
			W16-8	30x8	1.67			
619+00	RT	1	R1-1	36X36	9	26		
620+00	RT	1	R1-1	36X36	9	26		
637+64	RT	1	W14-3	36x48x48	5.5	26		
666+87	RT	1	W1-2	30x30	6.25	14.5		
687+05	RT	1	W3-3	30x30	6.25	14.5		

PAY ITEM NUMBER	DESCRIPTION		TOTAL QUANTITY	McHENRY COUNTY QUANTITY	CORAL ROAD QUANTITY	MARENGO/BECK/S. UNION ROADS QUANTITY	HARMONY ROAD QUANTITY	KANE COUNTY QUANTITY	I-90 RAMPS QUANTITY	ALLEN/BRIER HILL ROADS QUANTITY
85000300	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	L SUM	1	0				1	1	
88030012	SIGNAL HEAD, LED, 1-FACE, 1-SECTION, BRACKET MOUNTED	EACH	2	0				2	2	
88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	4	0				4	4	
88030070	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, BRACKET MOUNTED	EACH	2	0				2	2	
88030080	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED	EACH	2	0				2	2	
88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2	0				2	2	
88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	2	0				2	2	
88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	8	0				8	8	
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1	0				1	1	
X8803080	SIGNAL HEAD, LED, 1-FACE, 1-SECTION, BRACKET MOUNTED, RETROFIT	EACH	7	7	2	5		0		
XX003183	POST MOUNTED FLASHING BEACON INSTALLATION to FLASHING BEACON, POST MOUNTED, SOLAR POWERED INSTALLATION	EACH	10	6	2		4	4		4

P:\Jobs\2009\20090823-15\CAD\Site\Site.dgn 00:06:03T-sht-Schedule02.dgn
 2/11/2010 4:55:01PM

FILE NAME =	USER NAME = .USER.	DESIGNED - EF	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	US 20 - WEST UNION ROAD TO IL 47 SCHEDULE OF QUANTITIES - SIGNS AND TRAFFIC SIGNALS	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILEL*		DRAWN - EF	REVISED -			•	2009-089 I	••	46	5
PLOT SCALE = 50.0000' / IN.		CHECKED - RS	REVISED -			••	McHENRY & KANE			CONTRACT NO. 60J73
PLOT DATE = 2/11/2010		DATE - 02-08-2010	REVISED -			•	525/ 345	ILLINOIS	FED. AID PROJECT	
					SCALE: NTS	SHEET NO. 2 OF 2 SHEETS		STA. TO STA.		