

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	RDWY.		BRIDGE		DRAINAGE		CODE NO	ITEM	UNIT	TOTAL QUANTITIES	RDWY.		BRIDGE		DRAINAGE	
				I000-2A	SFTY-2A	I000-2A	SFTY-2A	I000-2A	SFTY-2A					I000-2A	SFTY-2A	I000-2A	SFTY-2A	I000-2A	SFTY-2A
70300560	PAVEMENT MARKING TAPE, TYPE III 12"	FOOT	12064			12064				* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	4217	4217					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	150,100	12278		143,890				* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1078	1078					
70400100	TEMPORARY CONCRETE BARRIER	FOOT	7237.5			7237.5				* 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	10394	10394					
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	6600			6600				X0320887	POLYMER CONCRETE	CU FT	2.2			2.2			
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	488.8	488.8						X0321743	SILICONE JOINT SEALER, 1"	FOOT	525			525			
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	146693	146693						X0321744	SILICONE JOINT SEALER, 2"	FOOT	519			519			
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1800	1800						X0322256	TEMPORARY INFORMATION SIGNING	SO FT	100			100			
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	63050	63050						* X0322300	ELECTRIC CABLE IN CONDUIT NO. 18 4/C, TWISTED, SHIELDED	FOOT	6177	6177					
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	14362	14362						X0322729	MATERIAL TRANSFER DEVICE	TON	83638	83638					
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	215	215						X0322933	SILICONE JOINT SEALER, 2.5"	FOOT	40			40			
* 78004200	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LETTERS AND SYMBOLS	SO FT	233.7	233.7						X0323076	SILICONE JOINT SEALER, 1 3/4"	FOOT	209			209			
* 78004220	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 5"	FOOT	39316	39316						X0323818	CLEANING AND PAINTING EXPOSED REBAR	SO FT	3248			3248			
* 78004240	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 8"	FOOT	625	625						X0324685	TEST STRIP (STONE MATRIX ASPHALT)	EACH	2	2					
* 78005120	EPOXY PAVEMENT MARKING - LINE 5"	FOOT	78632	78632						X0325201	SHOULDER RUMBLE STRIP REMOVAL	SO YD	6262			6262			
* 78005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	1250	1250						X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SO FT	451			451			
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	80951	72889	8062					X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SO FT	2769			2769			
* 78008220	POLYUREA PAVEMENT MARKING TYPE I - LINE 5"	FOOT	8217	6085	2132					X0325702	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1					
* 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	950	950						X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	4567			4567			
* 78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	4827	4265	562					X0325876	WET REFLECTIVE TEMPORARY TAPE TYPE III, 8 INCH	FOOT	625	625					
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	9972	6754	3218					X0326107	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 5 INCH	FOOT	68659	39316	29343				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	4868	4868						<del>X0603153</del>	<del>POLYMERIZED HOT MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, NO.</del>	<del>TON</del>	<del>41819</del>	<del>41819</del>					
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	232		232					<del>X0603148</del>	<del>POLYMERIZED HOT MIX ASPHALT BINDER COURSE, STONE MATRIX ASPHALT, NO.</del>	<del>TON</del>	<del>11819</del>	<del>11819</del>					
* 78200420	GUARDRAIL MARKERS, TYPE B	EACH	2716		2716					X4421000	PARTIAL DEPTH PATCHING	TON	62	62					
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	2356		2356					X4422030	PARTIAL DEPTH REMOVAL 3"	SO YD	365	365					
78300100	PAVEMENT MARKING REMOVAL	SO FT	44104		44104					X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	0.5	0.5				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	4127	3895	232					X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	20		20				
* 81017515	CONDUIT IN TRENCH, 1 1/4" DIA., COILABLE NONMETALLIC CONDUIT	FOOT	100	100						* X8850102	INDUCTION LOOP	FOOT	2065	2065					
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	100	100						X0326874	SILICONE JOINT SEALER, 3"	FOOT	287			287			
										Z0001800	APPROACH SLAB REPAIR (PARTIAL DEPTH)	SO YD	29.9			29.9			

\* SPECIALTY ITEM