

SUMMARY OF QUANTITIES			TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
CODE NO.	ITEM DESCRIPTION	UNIT	100% STATE	I000 QUANTITY	
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SO YD	250	250	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	59	59	
40600300	AGGREGATE (PRIME COAT)	TON	293	293	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	225	225	
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	5200	5200	
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	5951	5951	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	28	28	
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	14350	14350	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	190	190	
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SO YD	250	250	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	1250	1250	
42400800	DETECTABLE WARNINGS	SO FT	72	72	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	750	750	
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	660	660	
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	500	500	
44000600	SIDEWALK REMOVAL	SO FT	1250	1250	
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	7500	7500	
44003100	MEDIAN REMOVAL	SO FT	13370	13370	
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SO FT	104495	104495	
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SO YD	29	29	
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	4589	4589	
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	283	283	
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	1136	1136	
55039700	STORM SEWERS TO BE CLEANED	FOOT	1428	1428	
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	34	34	
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	15	15	
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	29	29	
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	212	212	

SUMMARY OF QUANTITIES			TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
CODE NO.	ITEM DESCRIPTION	UNIT	100% STATE	I000 QUANTITY	
60404940	FRAMES AND GRATES, TYPE 23	EACH	3	3	
60404950	FRAMES AND GRATES, TYPE 24	EACH	5	5	
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	6	6	
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	65	65	
60618740	CONCRETE MEDIAN, TYPE M-2.12	SO FT	3004	3004	
60620800	CONCRETE MEDIAN, TYPE SB-9.12	SO FT	6740	6740	
60624600	CORRUGATED MEDIAN	SO FT	3627	3627	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1	
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1	
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6	6	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	35305	35305	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	2085	2085	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	140560	140560	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	13220	13220	
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	2215	2215	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	6210	6210	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	3300	3300	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	11770	11770	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	1041	1041	

* SPECIALTY ITEM

FILE NAME : P:\2009\ME09006-Var-1\PH1\CADD\WDL\US45\Shs\03-D160166-shr-US45-500.dgn
 USER NAME : Millennium Professional Services



200 22ND Street, Suite 216, Lombard, IL 60148
 630.785.0110 voice, 630.839.2566 fax
 WWW.MPS-IL.COM

MILLENNIA PROFESSIONAL SERVICES

DESIGNED - CJD	REVISED -
DRAWN - CJD	REVISED -
CHECKED - TVN	REVISED -
DATE - 2/9/2010	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

US RTE 12/45
 BERTEAU AVE TO US RTE 20

SUMMARY OF QUANTITIES

F.A.P. RTE. 330	SECTION (464Y & 465Y) RS-3	COUNTY COOK	TOTAL SHEETS 44	SHEET NO. 3
CONTRACT NO. 60166			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT	

SCALE: NTS SHEET NO. OF SHEETS STA. TO STA.