SUMMARY OF QUANTITIES

	CODE NO.	ITEM DESCRIPTION	UNIT	URBAN 100% STATE TOTAL QUANTITY	CONSTRUCTION TYPE CODE 1000 QUANTITY	
•	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	70280	70280	
•	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	6610	6610	
•	78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1110	1110	
•	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	3105	3105	
•	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1650	1650	
•	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2810	2810	
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	2810	2810	
•	88600600	DETECTOR LOOP REPLACEMENT	FOOT	7679	7679	
	X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	416	416	
	X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	22685	22685	
	X4421000	PARTIAL DEPTH PATCHING	TON	225	225	
	X4422030	PARTIAL DEPTH REMOVAL 3"	SQ YD	1300	1300	
	X8950200	REBUILD EXISTING HANDHOLE	EACH	8	8	
	X8950210	REBUILD EXISTING HANDHOLE TO HEAVY-DUTY HANDHOLE	EACH	9	9	
	Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	183	183	
	Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	
•	X0326864	BRICK SIDEWALK REMOVAL	SQ FT	3500	3500	
•	X0326863	BRICK SIDEWALK	SQ FT	3500	3500	
	Z0075310	TIE BARS 3/4"	EACH	3420	3420	
	XZ043900	PREFORMED JOINT FILLER REMOVAL	FOOT	25700	25700	

• SPECIALTY ITEM

MILLENNIA PROFESSIONAL SERVICES
380 22ND Street, Suite 216, Lombard, IL 60148
630.705.0110 voice, 630.839.2566 fax
WWW.MPS-IL.COM

DESIGNED	CJD	REVISED	-
DRAWN	CJD	REVISED	-
CHECKED	TVN	REVISED	-
DATE	2/9/2010	REVISED	-

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

US RTE 12/45
BERTEAU AVE TO US RTE 20

SCALE: · SHEET NO. OF SHEETS STA. · TO STA.

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	(464Y & 465Y) RS-3	COOK	44	3A
		CONTRACT NO. 60166		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

P:\2009\ME09006.VarVar Phil\CADD\W01.US45\Shts\03-D160166-sht-US45-S00.dgn

FILE NAME = P:\2009\ME09006.VarVar Phil\CADD\W01.US45\Shts\03-D160166-sht-US45-S00.dgn
SCALE = 1:2000 / 1" = 200'
USER NAME = Millennia Professional Services