

SUMMARY OF QUANTITIES			URBAN	
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE
			80% FED. 20% STATE	1000 QUANTITY
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	46	46
40600300	AGGREGATE (PRIME COAT)	TON	229	229
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	172	172
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	2557	2557
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	3894	3894
40600895	CONSTRUCTING TEST STRIP	EACH	1	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT	SQ YD	42	42
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	3235	3235
40603153	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	12,915	12,915
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2,127	2,127
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	21697	21697
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	100	100
44003100	MEDIAN REMOVAL	SQ FT	3612	3612
44201773	CLASS D PATCHES, TYPE I, 11 INCH	SQ YD	50	50
44201777	CLASS D PATCHES, TYPE II, 11 INCH	SQ YD	1574	1574
44201781	CLASS D PATCHES, TYPE III, 11 INCH	SQ YD	50	50
44201783	CLASS D PATCHES, TYPE IV, 11 INCH	SQ YD	370	370
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	24295	24295
Δ 55039700	STORM SEWERS TO BE CLEANED	FOOT	1728	1728
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	9	9
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	5	5
60300105	FRAME AND GRATES TO BE ADJUSTED	EACH	7	7
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	67	67
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	39	39
60404950	FRAMES AND GRATES, TYPE 24	EACH	10	10
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	10	10
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	10	10
60624600	CORRUGATED MEDIAN	SQ FT	3297	3297
60622800	CONCRETE MEDIAN, TYPE SM-6.12	SQ FT	315	315
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6

SUMMARY OF QUANTITIES			URBAN	
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE
			80% FED. 20% STATE	1000 QUANTITY
67100100	MOBILIZATION	L SUM	1	1
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	8990	8990
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	2260	2260
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	66220	66220
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	9040	9040
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	4660	4660
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	4240	4240
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	1440	1440
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1498	1498
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	1130	1130
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	33110	33110
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	4520	4520
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	2330	2330
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2120	2120
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	720	720
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1396	1396
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	88	88
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1396	1396
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	2482	2482
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	104	104
X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SO YD	15787	15787
X8950210	REBUILD EXISTING HANDHOLE TO HEAVY-DUTY HANDHOLE	EACH	4	4
Δ Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	487	487
XZ043900	PREFORMED JOINT FILLER REMOVAL	FOOT	21720	21720
X0324685	TEST STRIP (STONE MATRIX ASPHALT)	EACH	1	1
	Δ Non-participating			
	* Specialty Items			

\* SPECIALTY ITEM

FILE NAME : P:\2009\ME0906-Var\Var-Phil\CADD\W07\_IL83N\Shs\03-D160J20-shr-IL83N-500.dgn  
 USER NAME : Millennium Professional Services



200 22ND Street, Suite 216, Lombard, IL 60148  
 630.785.8110 voice, 630.839.2566 fax  
 WWW.MPS-IL.COM  
**MILLENNIA PROFESSIONAL SERVICES**

DESIGNED - CJD	REVISED -
DRAWN - CJD	REVISED -
CHECKED - RPD	REVISED -
DATE - 2/23/2010	REVISED -

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**ILLINOIS ROUTE 83 (NORTH)**  
**WASHINGTON ST TO ILLINOIS RTE 64**

**SUMMARY OF QUANTITIES**

F.A.P. RTE. 344	SECTION 543 X-RS-2	COUNTY DUPAGE	TOTAL SHEETS 30	SHEET NO. 3
CONTRACT NO. 60J20			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT	

SCALE: NTS SHEET NO. OF SHEETS STA. TO STA.

P:\2009\ME0906-Var\Var-Phil\CADD\W07\_IL83N\Shs\03-D160J20-shr-IL83N-500.dgn