

SUMMARY OF QUANTITIES			80% FED. 20% STATE	SUMMARY OF QUANTITIES			80% FED. 20% STATE	SUMMARY OF QUANTITIES			80% FED. 20% STATE
CODE NO.	ITEM	UNIT	URBAN TOTAL	ROADWAY 1000	BRIDGE X020-2A	CODE NO.	ITEM	UNIT	URBAN TOTAL	ROADWAY 1000	BRIDGE X020-2A
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1	1		* 78000100	THERMOPLASTIC PAVEMENT MARKING-LETTERS AND SYMBOLS	SQ FT	182	182	
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	25	25		* 78000200	THERMOPLASTIC PAVEMENT MARKING-LINE 4"	FOOT	7043	6909	134
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	50	50		* 78000400	THERMOPLASTIC PAVEMENT MARKING-LINE 6"	FOOT	1503	1503	
44000100	PAVEMENT REMOVAL	SQ YD	36	36		* 78000600	THERMOPLASTIC PAVEMENT MARKING-LINE 12"	FOOT	103	103	
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	589	589		* 78000650	THERMOPLASTIC PAVEMENT MARKING-LINE 24"	FOOT	87	87	
44000915	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	180		180	* <del>78000810</del>	<del>POLYUREA PAVEMENT MARKING TYPE I - LINE 4"</del>	<del>FOOT</del>	<del>134</del>		<del>134</del>
44003900	<sup>SURFACE</sup> MEDIAN REMOVAL AND REPLACEMENT	SQ FT	317	317		* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	4	4	
50102400	CONCRETE REMOVAL	CU YD	21.2		21.2	* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	18	18	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	21.7		21.7	* 78300100	PAVEMENT MARKING REMOVAL	SQ FT	3394	3394	
50300260	BRIDGE DECK GROOVING	SQ YD	172		172	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	4		4
50300300	PROTECTIVE COAT	SQ YD	218		218	X0320887	POLYMER CONCRETE	CU FT	6.1		6.1
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	4880		4880	X0322185	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/4 INCHES	SQ YD	182		182
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6		X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52	
67100100	MOBILIZATION	L SUM	1	1		X0325303	STRUCTURAL REPAIR OF CONCRETE (GREATER THAN 5 INCHES) <sup>DEPTH</sup>	SQ FT	14		14
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1		X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	80		80
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	20	20		X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	12808	12808	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6	6		X0325837	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 6 INCH	FOOT	66	66	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	405	405		X0325841	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 24 INCH	FOOT	64	64	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	405	405		X0325842	WET REFLECTIVE TEMPORARY TAPE, TYPE III, LETTERS AND SYMBOLS	SQ FT	36	36	

\* SPECIALTY ITEMS

**LONCO, INC.**  
CONSULTING ENGINEERS  
1560 WALL ST, SUITE 222  
NAPERVILLE, ILLINOIS 60563 PH 630/ 511-9100

DESIGNED - MJY  
DRAWN - ST, TSC  
CHECKED - MJY, DC  
DATE - 01/29/2010

REVISED -  
REVISED -  
REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES  
US 6 (159th STREET) OVER CALUMET UNION DITCH

SCALE: NONE SHEET NO. 3 OF 21 SHEETS STA. 91+81.22 TO STA. 92+79.51

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
351	539 B-1	COOK	21	3
D-91-226-10		CONTRACT NO. 60J36		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		