

SUMMARY OF QUANTITIES			80% FED. 20% STATE			SUMMARY OF QUANTITIES			80% FED. 20% STATE		
CODE NO.	ITEM	UNIT	URBAN TOTAL	ROADWAY J000-2A	BRIDGE X321-2A	CODE NO.	ITEM	UNIT	URBAN TOTAL	ROADWAY J000-2A	BRIDGE X321-2A
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	5340	5340		67100100	MOBILIZATION	L SUM	1	1	
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	148	148		70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	460	460		70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1	
40701921	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 12"	SQ YD	140	140		70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	40	40	
44000100	PAVEMENT REMOVAL	SQ YD	140	140		70106800	CHANGEABLE MESSAGE SIGN	CAL MO	12	12	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	1967	1967		70400100	TEMPORARY CONCRETE BARRIER	FOOT	3825	3825	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	3245	3245		70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	3663	3663	
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	257	257		* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	12294	12294	
50102400	CONCRETE REMOVAL	CU YD	80.5		80.5	* 78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	468	468	
50157300	PROTECTIVE SHIELD	SQ YD	7732		7732	* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	70	70	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	92.3		92.3	* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	48	48	
50300260	BRIDGE DECK GROOVING	SQ YD	11439		11439	* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	140		140
50300300	PROTECTIVE COAT	SQ YD	12166		12166	* 78100300	REPLACEMENT REFLECTOR	EACH	38	38	
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	14290		14290	* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	1224	1224	
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	80		80	78300100	PAVEMENT MARKING REMOVAL	SQ FT	3679	3679	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	18010		18010	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	188	48	140
50800515	BAR SPLICERS	EACH	194		194	X0322185	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/4 INCHES	SQ YD	11918		11918
52000110	PREFORMED JOINT STRIP SEAL	FOOT	100		100	X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	200	200	
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	80		80	X0322467	TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE	SQ FT	200	200	
52100520	ANCHOR BOLTS, 1"	EACH	160		160	X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	19065	19065	

* SPECIALTY ITEMS

LONCO, INC.
CONSULTING ENGINEERS
1560 WALL ST., SUITE 222
NAPERVILLE, ILLINOIS 60563 PH 16301 577-9100

DESIGNED - MJY	REVISED -
DRAWN - ST, TSC	REVISED -
CHECKED - MJY, DC	REVISED -
DATE - 01/29/2010	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES
US 12, 20, 45 SB (LA GRANGE RD) OVER SANTA FE DR, RRs, DES PLAINES**

SCALE: NONE SHEET NO. 3 OF 54 SHEETS STA. 31+99.36 TO STA. 69+00.70

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	462 X-B-1	COOK	54	3
D-91-227-10			CONTRACT NO. 60J37	
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				