



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 15, 2010

SUBJECT: FAP Route 330 (US 12/20/45, LaGrange Rd.)
Project ACNHF-0330 (062)
Section 462X-B-I-1
Cook County
Contract No. 60J38
Item No. 273, April 23, 2010 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Replaced the Schedule of Prices.
2. Revised page ii of the Table of Contents to the Special Provisions.
3. Added page 102 to the Special Provisions.
4. Revised sheets 3, 11, 12, 13 & 14 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Scott E. Stitt, P.E.
Acting Engineer of Design and Environment

A handwritten signature in cursive script, appearing to read 'Ted B. Walschleger', followed by the initials 'P.E.'.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Diane O'Keefe, Region 1, District 1; Mike Renner; R. E. Anderson;
Estimates

TBW:MS:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60J38

State Job # - C 91-228-10
 PPS NBR - 1-78356-0000
 County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - 462X-B-I-1

Project Number
 ACNHF-0330/062/

Route
 FAP 330

* Revised April 15, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X0322185	BR DK LTX C OLY 2 1/4	SQ YD	5,883.000				
* X0322256	TEMP INFO SIGNING	SQ FT	206.000				
X0325305	STR REP CON DP = < 5	SQ FT	213.000				
X0325775	WET RF TEM TAPE T3 4	FOOT	7,731.000				
Z0006204	BR DECK HY-SCAR 1/2	SQ YD	5,883.000				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.000				
Z0016002	DECK SLAB REP (FD-T2)	SQ YD	23.000				
Z0034390	MODULAR EXPAN JT 6	FOOT	42.000				
Z0048665	RR PROT LIABILITY INS	L SUM	1.000				
40600200	BIT MATLS PR CT	TON	1.000				
40600635	LEV BIND MM N70	TON	22.000				
40603595	P HMA SC "F" N90	TON	59.000				
44000155	HMA SURF REM 1 1/2	SQ YD	268.000				
44000198	HMA SURF REM VAR DP	SQ YD	332.000				
50102400	CONC REM	CU YD	36.500				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60J38

State Job # - C 91-228-10
 PPS NBR - 1-78356-0000
 County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - 462X-B-I-1

Project Number
 ACNHF-0330/062/

Route
 FAP 330

* Revised April 15, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
50157300	PROTECTIVE SHIELD	SQ YD	2,152.000				
50300255	CONC SUP-STR	CU YD	41.800				
50300260	BR DECK GROOVING	SQ YD	5,967.000				
50300300	PROTECTIVE COAT	SQ YD	5,985.000				
50500405	F & E STRUCT STEEL	POUND	7,833.000				
50500715	JACK & REM EX BEARING	EACH	35.000				
50800205	REINF BARS, EPOXY CTD	POUND	5,940.000				
50800515	BAR SPLICERS	EACH	91.000				
52000110	PREF JT STRIP SEAL	FOOT	168.000				
52100010	ELAST BEARING ASSY T1	EACH	10.000				
52100020	ELAST BEARING ASSY T2	EACH	20.000				
52100030	ELAST BEARING ASSY T3	EACH	5.000				
52100520	ANCHOR BOLTS 1	EACH	90.000				
67000400	ENGR FIELD OFFICE A	CAL MO	8.000				
67100100	MOBILIZATION	L SUM	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60J38

State Job # - C 91-228-10
 PPS NBR - 1-78356-0000
 County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - 462X-B-I-1

Project Number
 ACNHF-0330/062/

Route
 FAP 330

* Revised April 15, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
70101800	TRAF CONT & PROT SPL	L SUM	1.000				
70102550	TR CONT-PROT TEMP DET	EACH	1.000				
70103815	TR CONT SURVEILLANCE	CAL DA	40.000				
70106800	CHANGEABLE MESSAGE SN	CAL MO	12.000				
70400100	TEMP CONC BARRIER	FOOT	1,732.000				
70400200	REL TEMP CONC BARRIER	FOOT	1,732.000				
78008210	POLYUREA PM T1 LN 4	FOOT	4,846.000				
78100100	RAISED REFL PAVT MKR	EACH	32.000				
78100105	RAISED REF PVT MKR BR	EACH	68.000				
78200530	BAR WALL MKR TYPE C	EACH	71.000				
78300100	PAVT MARKING REMOVAL	SQ FT	1,616.000				
78300200	RAISED REF PVT MK REM	EACH	100.000				

EQUIPMENT RENTAL RATES (BDE)..... 77

FLAGGER AT SIDE ROADS AND ENTRANCES (BDE) 78

HOT-MIX ASPHALT – ANTI-STRIPPING ADDITIVE (BDE) 79

HOT-MIX ASPHALT - DENSITY TESTING OF LONGITUDINAL JOINTS (BDE) 79

HOT-MIX ASPHALT – DROP-OFFS (BDE) 80

HOT-MIX ASPHALT – PLANT TEST FREQUENCY (BDE) 80

HOT-MIX ASPHALT – QC/QA ACCEPTANCE CRITERIA (BDE) 81

HOT-MIX ASPHALT – TRANSPORTATION (BDE) 82

IMPACT ATTENUATORS, TEMPORARY (BDE) 82

LIQUIDATED DAMAGES (BDE)..... 84

MONTHLY EMPLOYMENT REPORT (BDE) 84

NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM / EROSION AND SEDIMENT CONTROL DEFICIENCY DEDUCTION (BDE) 85

NOTIFICATION OF REDUCED WIDTH (BDE) 86

PAVEMENT MARKING REMOVAL (BDE) 86

PAYMENTS TO SUBCONTRACTORS (BDE) 87

PERSONAL PROTECTIVE EQUIPMENT (BDE) 88

POLYUREA PAVEMENT MARKING (BDE) 88

PORTLAND CEMENT CONCRETE PLANTS (BDE) 95

RAISED REFLECTIVE PAVEMENT MARKERS (BDE) 96

REFLECTIVE SHEETING ON CHANNELIZING DEVICES (BDE) 96

REINFORCEMENT BARS - STORAGE AND PROTECTION (BDE)..... 97

SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) 97

TRUCK MOUNTED/TRAILER MOUNTED ATTENUATORS (BDE) 97

STEEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID) 98

HOT MIX ASPHALT MIXTURES, EGA MODIFIED PERFORMANCE GRADED (PG) ASPHALT BINDER 102

Revised 04/15/2010

HOT MIX ASPHALT MIXTURES, EGA MODIFIED PERFORMANCE GRADED (PG) ASPHALT BINDER

Effective: March 16, 2009

Description. This work shall consist of constructing Hot Mix Asphalt (HMA) mixtures containing ethylene-glycidyl-acrylate (EGA) Modified Performance Graded (PG) Asphalt Binder. Work shall be according to Sections 406, 1030, and 1032 of the Standard Specifications, except as modified herein.

The asphalt binder shall meet the following requirements:

EGA Modified Performance Graded (PG) Asphalt Binder. The asphalt binder shall meet the requirements of AASHTO M 320, Table 1 "Standard Specification for Performance Graded Asphalt Binder" for the grade shown on the plans. An ethylene-glycidyl-acrylate (EGA) terpolymer with a maximum of 0.3 percent polyphosphoric acid by weight of asphalt binder, shall be added to the base asphalt binder to achieve the specified performance grade. Asphalt modification at hot-mix asphalt plants will not be allowed. The modified asphalt binder shall be smooth, homogeneous, and be according to the requirements shown in the following table for the grade shown on the plans.

Ethylene-Glycidyl-Acrylate (EGA) Modified Asphalt Binders		
Test	Asphalt Grade EGA PG 70-22 EGA PG 70-28	Asphalt Grade EGA PG 76-22 EGA PG 76-28
Separation of Polymer Illinois Test Procedure, "Separation of Polymer from Asphalt Binder" Difference in °F (°C) of the softening point between top and bottom portions.	4 (2) max.	4 (2) max.
TEST ON RESIDUE FROM ROLLING THIN FILM OVEN TEST (AASHTO T 240)		
Elastic Recovery ASTM D 6084, Procedure A, 77 °F (25 °C), 100 mm elongation, %	60 min.	70 min.

Added 04/15/2010