

URBAN
80% FED.
20% STATE

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE BRIDGE SN 016-0322	
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	SFTY-2A QUANTITY	
31100200	SUB-BASE GRANULAR MATERIAL, TYPE A	CU YD	208	208	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1	1	
40600300	AGGREGATE (PRIME COAT)	TON	2	2	
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
40603395	HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	82	82	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	974	974	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	619	619	
44000915	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	1,134	1,134	
44003100	MEDIAN REMOVAL	SQ FT	5,077	5,077	
44003700	MEDIAN REMOVAL (SPECIAL)	SQ FT	2,706	2,706	
50102400	CONCRETE REMOVAL	CU YD	75.4	75.4	
50300100	FLOOR DRAINS	EACH	29	29	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	78	78	
50300260	BRIDGE DECK GROOVING	SQ YD	1,064	1,064	
50300300	PROTECTIVE COAT	SQ YD	1,193	1,193	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	12,480	12,480	
50800515	BAR SPLICERS	EACH	22	22	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	181	181	
58700300	CONCRETE SEALER	SQ FT	6,950	6,950	
60605600	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.06	FOOT	6,950	6,950	
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	4,811	4,811	
60620400	CONCRETE MEDIAN, TYPE SB-9.06	SQ FT	2,706	2,706	
60624600	CORRUGATED MEDIAN	SQ FT	266	266	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1,154	1,154	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	21,608	21,608	
* 72000100	SIGN PANEL - TYPE 1	SQ FT	15	15	
* 72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	3	3	
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	41	41	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	110	110	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	5,632	5,632	

* SPECIALTY ITEM

URBAN
80% FED.
20% STATE

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE BRIDGE SN 016-0322	
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	SFTY-2A QUANTITY	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	459	459	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	38	38	
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	1,220	1,220	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	246	246	
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	10	10	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	2,293	2,293	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	222	222	
X0326766	CLEAN & RESEAL RELIEF JOINT	FOOT	150	150	
X0322185	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/4 INCHES	SQ YD	1,134	1,134	
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	103	103	
X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	20,454	20,454	
X0712400	TEMPORARY PAVEMENT	SQ YD	569	569	
X0919000	TEMPORARY PAVEMENT REMOVAL	SQ YD	569	569	
70006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2"	SQ YD	1,134	1,134	
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	7.5	7.5	
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	10	10	
50157800	PROTECTIVE SHIELD	SQ YD	1745	1745	

* SPECIALTY ITEM

PLOT DATE = 1/28/2010
FILE NAME = K:\11225222\CAD\Sheets\1172_500.dgn
PLOT SCALE = 1:1
USER = djw
JOB = 1172



Excellence through Ownership

200 West Front Street
Wheaton, IL 60187

DESIGNED - MTH
DRAWN - DJW
CHECKED - MAK
DATE - 1/28/2010 6:25:37 PM

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL-72 OVER DESPLAINES RIVER
SN 016-0665

SCALE: 1

SHEET NO. 3 OF 33 SHEETS

SUMMARY OF QUANTITIES

STA. TO STA.

Rev.
F.A.U. SECTION COUNTY TOTAL SHEETS SHEET NO.
1350 1292-1 COOK 33 3
CONTRACT NO. 60J57
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT