

URBAN

URBAN

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT	TOTAL QUANTITIES 100% STATE	I000						CODE NO	ITEM	UNIT	TOTAL QUANTITIES 100% STATE	I000					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	31	31						70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	571	571					
40600300	AGGREGATE (PRIME COAT)	TON	156	156						70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	1689	1689					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	59	59						70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	800	800					
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1838	1838						70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	49	49					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2						70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2382	2382					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	185	185						*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	146	146					
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	160	160						*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	32028	32028					
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	593	593						*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	571	571					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3856	3856						*78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1689	1689					
42001300	PROTECTIVE COAT	SQ YD	45	45						*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	800	800					
44000153	HOT-MIX ASPHALT SURFACE REMOVAL, 1"	SQ YD	3527	3527						*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	49	49					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	35450	35450						*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	323	323					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	75	75						78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	280	280					
44003100	MEDIAN REMOVAL	SQ FT	250	250						X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4					
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	90	90						Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	5	5					
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	50	50															
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	158	158															
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	480	480															
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	496	496															
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	400	400															
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	5	5															
60619200	CONCRETE MEDIAN, TYPE SB-6.06	SQ FT	250	250															
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6															
67100100	MOBILIZATION	L SUM	1	1															
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1															
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1															
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1															
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	7147	7147															
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	146	146															
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	32028	32028															

SPECIALTY ITEMS