

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	I000					CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	I000				
20200100	EARTH EXCAVATION	CU YD	30	30					70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1				
20201006	GRADING AND SHAPING SHOULDERS	UNIT	420	420					70300100	SHORT-TERM PAVEMENT MARKING	FOOT	11446	11446				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	56	56					70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	485	485				
25200110	SODDING, SALT TOLERANT	SQ YD	56	56					70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	81918	81918				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	73	73					70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2158	2158				
40600300	AGGREGATE (PRIME COAT)	TON	362	362					70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1001	1001				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	136	136					70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	343	343				
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4, 75, N50	TON	3731	3731					70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3816	3816				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2				* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	485	485					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	174	174				* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	81918	81918					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	7597	7597				* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2158	2158					
42001300	PROTECTIVE COAT	SQ YD	84	84				* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1001	1001					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	90429	90429				* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	343	343					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	250	250				* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1050	1050					
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	120	120				* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	23	23					
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	1500	1500				78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1050	1050					
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	700	700				* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1252	1252					
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	250	250				X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	154.2	154.2					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1376	1376				Z0018400	DRAINAGE STRUCTURES TO BE ADJUSTED	EACH	4	4					
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	176	176				Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	40	40					
55039700	STORM SEWERS TO BE CLEANED	FOOT	500	500				Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1					
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	1	1													
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	23	23													
63200310	GUARDRAIL REMOVAL	FOOT	1150	1150													
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6													
67100100	MOBILIZATION	L SUM	1	1													
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1													
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1													

* - Specialty Items

FILE NAME =	USER NAME = ulrchk	DESIGNED -	REVISED -
CA:\work\PWIDT\ULRCHK\DI015499\DI25510-sht-pndgn		DRAWN -	REVISED -
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -
PLOT DATE = 1/27/2010		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL. RTE. 173
SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	136RS-6	LAKE	28	3
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60J65	

Rev.