

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY		CONSTRUCTION TYPE CODE
			100% STATE	1000 QUANTITY	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	110	110	
25200110	SODDING, SALT TOLERANT	SO YD	110	110	
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SO YD	180	180	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	21	21	
40600300	AGGREGATE (PRIME COAT)	TON	104	104	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	78	78	
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2110	2110	
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT	SO YD	478	478	
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	591	591	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	21	21	
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	5194	5194	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	5	5	
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SO YD	180	180	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	500	500	
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	51630	51630	
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	1366	1366	
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	180	180	
44000600	SIDEWALK REMOVAL	SO FT	500	500	
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	610	610	
44002213	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3 1/4"	SO YD	3250	3250	
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	1520	1520	
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	350	350	
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	1190	1190	
55039700	STORM SEWERS TO BE CLEANED	FOOT	402	402	
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	11	11	
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	5	5	
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	7	7	
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	7	7	

* SPECIALTY ITEM

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY		CONSTRUCTION TYPE CODE
			100% STATE	1000 QUANTITY	
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	66	66	
60404940	FRAMES AND GRATES, TYPE 23	EACH	5	5	
60404950	FRAMES AND GRATES, TYPE 24	EACH	5	5	
60406520	FRAMES AND LIDS, OPEN LID (CITY OF CHICAGO)	EACH	15	15	
60406530	FRAMES AND LIDS, CLOSED LID (CITY OF CHICAGO)	EACH	15	15	
40600990	TEMPORARY RAMP	SO YD	150	150	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1	
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1	
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4290	4290	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	1630	1630	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	50145	50145	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	13100	13100	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	6025	6025	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	1350	1350	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	715	715	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	815	815	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	23830	23830	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	6550	6550	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	3015	3015	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	675	675	
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	791	791	
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	52	52	
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	133	133	

P:\2009\ME09086-Var-Vor-Phit\CADD\W01_CottageGr-A\Shets\04-D168J68-ant-CottageGr-SDD.dgn
 FILE NAME =
 USER NAME =
 MILLERNA Professional Services



200 22ND Street, Suite 216, Lombard, IL 60148
 630.785.0110 voice, 630.839.2566 fax
 WWW.MPS-IL.COM

MILLENNIA PROFESSIONAL SERVICES

DESIGNED - CJD
 DRAWN - CJD
 CHECKED - RPD
 DATE - 2/15/2010

REVISED -
 REVISED -
 REVISED -
 REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

**COTTAGE GROVE AVENUE
 83RD STREET TO 92ND STREET**

SUMMARY OF QUANTITIES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2919	2009-118 RS	COOK	29	4
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60J68	

SCALE: NTS SHEET NO. OF SHEETS STA. TO STA.

P:\2009\ME09086-Var-Vor-Phit\CADD\W01_CottageGr-A\Shets\04-D168J68-ant-CottageGr-SDD.dgn