

| SUMMARY OF QUANTITIES | | | 100% STATE | CONSTRUCTION TYPE CODE | | | | | SUMMARY OF QUANTITIES | | | 100% STATE | CONSTRUCTION TYPE CODE | | | | |
|-----------------------|--|--------|------------------|------------------------|--|--|--|-----------|---|--|-------|------------------|------------------------|--|--|--|--|
| CODE NO | ITEM | UNIT | TOTAL QUANTITIES | URBAN 1000-2A | | | | | CODE NO | ITEM | UNIT | TOTAL QUANTITIES | URBAN 1000-2A | | | | |
| 21101615 | TOPSOIL FURNISH AND PLACE, 4" | SO YD | 417 | 417 | | | | | 78000100 | THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS | SO FT | 1065 | 1065 | | | | |
| 25200110 | SODDING, SALT TOLERANT | SO YD | 417 | 417 | | | | | 78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4" | FOOT | 13349 | 13349 | | | | |
| 40600200 | BITUMINOUS MATERIALS (PRIME COAT) | TON | 22 | 22 | | | | | 78000400 | THERMOPLASTIC PAVEMENT MARKING - LINE 6" | FOOT | 80 | 80 | | | | |
| 40600400 | MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS | TON | 40 | 40 | | | | | 78000600 | THERMOPLASTIC PAVEMENT MARKING - LINE 12" | FOOT | 660 | 660 | | | | |
| 40600826 | POLYMERIZED LEVELING BINDER (MACHINE METHOD), 1L-4.75, N50 | TON | 1108 | 1108 | | | | | 78000650 | THERMOPLASTIC PAVEMENT MARKING - LINE 24" | FOOT | 3900 | 3900 | | | | |
| 40600895 | CONSTRUCTING TEST STRIP | EACH | 1 | 1 | | | | | 78100100 | RAISED REFLECTIVE PAVEMENT MARKER | EACH | 198 | 198 | | | | |
| 40600982 | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT | SO YD | 173 | 173 | | | | | 78300200 | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL | EACH | 68 | 68 | | | | |
| 40601005 | HOT-MIX ASPHALT REPLACEMENT OVER PATCHES | TON | 298 | 298 | | | | | 88600600 | DETECTOR LOOP REPLACEMENT | FOOT | 570 | 570 | | | | |
| 40603340 | HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70 | TON | 2257 | 2257 | | | | X0322256 | TEMPORARY INFORMATION SIGNING | SO FT | 165 | 165 | | | | | |
| 42001300 | PROTECTIVE COAT | SO YD | 556 | 556 | | | | Z00486665 | RAILROAD PROTECTIVE LIABILITY INSURANCE | L SUM | 1 | 1 | | | | | |
| 44000158 | HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4" | SO YD | 26872 | 26872 | | | | 40600300 | AGGREGATE (PRIME COAT) | TON | 108 | 108 | | | | | |
| 44001700 | COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT | FOOT | 5000 | 5000 | | | | 60250200 | CATCH BASINS TO BE ADJUSTED | EACH | 10 | 10 | | | | | |
| 44002212 | HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3" | SO YD | 1774 | 1774 | | | | 60300305 | FRAMES AND LIDS TO BE ADJUSTED | EACH | 7 | 7 | | | | | |
| 44201753 | CLASS D PATCHES, TYPE II, 9 INCH | SO YD | 484 | 484 | | | | Z0018500 | DRAINAGE STRUCTURES TO BE CLEANED | EACH | 42 | 42 | | | | | |
| 44201757 | CLASS D PATCHES, TYPE III, 9 INCH | SO YD | 484 | 484 | | | | | | | | | | | | | |
| 44201759 | CLASS D PATCHES, TYPE IV, 9 INCH | SO YD | 645 | 645 | | | | | | | | | | | | | |
| 60300310 | FRAMES AND LIDS TO BE ADJUSTED (SPECIAL) | EACH | 40 | 40 | | | | | | | | | | | | | |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 6 | 6 | | | | | | | | | | | | | |
| 67100100 | MOBILIZATION | L SUM | 1 | 1 | | | | | | | | | | | | | |
| 70102620 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701501 | L SUM | 1 | 1 | | | | | | | | | | | | | |
| 70102625 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701606 | L SUM | 1 | 1 | | | | | | | | | | | | | |
| 70102635 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701701 | L SUM | 1 | 1 | | | | | | | | | | | | | |
| 70300100 | SHORT-TERM PAVEMENT MARKING | FOOT | 5200 | 5200 | | | | | | | | | | | | | |
| 70300210 | TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS | SO FT | 1065 | 1065 | | | | | | | | | | | | | |
| 70300220 | TEMPORARY PAVEMENT MARKING - LINE 4" | FOOT | 11349 | 11349 | | | | | | | | | | | | | |
| 70300240 | TEMPORARY PAVEMENT MARKING - LINE 6" | FOOT | 80 | 80 | | | | | | | | | | | | | |
| 70300260 | TEMPORARY PAVEMENT MARKING - LINE 12" | FOOT | 660 | 660 | | | | | | | | | | | | | |
| 70300280 | TEMPORARY PAVEMENT MARKING - LINE 24" | FOOT | 390 | 390 | | | | | | | | | | | | | |

• SPECIALTY ITEMS

Rev.