

SUMMARY OF QUANTITIES			80% FED. 20% STATE			SUMMARY OF QUANTITIES			80% FED. 20% STATE		
CODE NO.	ITEM	UNIT	URBAN TOTAL	ROADWAY 1000	BRIDGE X281-2A	CODE NO.	ITEM	UNIT	URBAN TOTAL	ROADWAY 1000	BRIDGE X281-2A
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1	1		70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	52	52		70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	20	20	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	103	103		70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6	6	
44000100	PAVEMENT REMOVAL	SQ YD	129	129		70400100	TEMPORARY CONCRETE BARRIER	FOOT	1240	1240	
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	427		427	70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1240	1240	
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	778	778		* 78000200	THERMOPLASTIC PAVEMENT MARKING-LINE 4"	FOOT	5027	3841	1186
50102400	CONCRETE REMOVAL	CU YD	153.3		153.3	* 78000650	THERMOPLASTIC PAVEMENT MARKING-LINE 24"	FOOT	66	66	
50104650	SLOPE WALL REMOVAL	SQ YD	139		139	78008210	POLYUREA PAVEMENT MARKING TYPE 1-LINE 4"	FOOT	1186		1186
50157300	PROTECTIVE SHIELD	SQ YD	1451		1451	* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	4	4	
50300100	FLOOR DRAINS	EACH	12		12	* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	12		12
50300255	CONCRETE SUPERSTRUCTURE	CU YD	168.4		168.4	* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	51	51	
50300260	BRIDGE DECK GROOVING	SQ YD	1995		1995	78300100	PAVEMENT MARKING REMOVAL	SQ FT	1305	1305	
50300300	PROTECTIVE COAT	SQ YD	2247		2247	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	16	4	12
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	27,060		27,060	X0322185	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/4 INCHES	SQ YD	1938		1938
50800515	BAR SPLICERS	EACH	160		160	X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52	
51100100	SLOPE WALL, 4 INCH	SQ YD	175		175	X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	20		20
52000110	PREFORMED JOINT STRIP SEAL	FOOT	505		505	X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	10097	10097	
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	59		59	X0325841	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 24 INCH	FOOT	32	32	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6		X0712400	TEMPORARY PAVEMENT	SQ YD	129	129	
67100100	MOBILIZATION	L SUM	1	1		*5000600	MECHANICAL SPLICERS	EACH	312		312

* SPECIALTY ITEMS

LONCO, INC.
CONSULTING ENGINEERS
1560 WALL ST, SUITE 222
NAPERVILLE, ILLINOIS 60563 PH (630) 577-9100

DESIGNED - MJY	REVISED -
DRAWN - ST, TSC	REVISED -
CHECKED - MJY, DC	REVISED -
DATE - 01/29/2010	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
YORK ROAD AT IL ROUTE 38 (1.5 MI EAST OF IL ROUTE 83)

SCALE: NONE SHEET NO. 3 OF 31 SHEETS STA. 58+35 TO STA. 61+67

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2678	163 HB-1-1	DUPAGE	31	3
D-91-275-10		CONTRACT NO. 60J85		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		