

URBAN

SUMMARY OF QUANTITIES			TOTAL QUANTITY	CONSTRUCTION TYPE CODE
CODE NO.	ITEM DESCRIPTION	UNIT	100% STATE	1000 QUANTITY
20201006	GRADING AND SHAPING SHOULDERS	UNIT	207	207
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	18	18
40600300	AGGREGATE (PRIME COAT)	TON	87	87
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	65	65
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1824	1824
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT	SQ YD	365	365
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	938	938
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	4290	4290
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	43780	43780
44002224	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 6"	SQ YD	2791	2791
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	64	64
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	1243	1243
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	285	285
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	949	949
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	826	826
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	5	5
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1
* 70300100	SHORT-TERM PAVEMENT MARKING	FOOT	5146	5146
* 70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	18	18
* 70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	76620	76620
* 70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2915	2915
* 70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	870	870
* 70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	310	310
* 70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	858	858
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	9	9

* SPECIALTY ITEM

URBAN

SUMMARY OF QUANTITIES			TOTAL QUANTITY	CONSTRUCTION TYPE CODE
CODE NO.	ITEM DESCRIPTION	UNIT	100% STATE	1000 QUANTITY
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	38310	38310
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1460	1460
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	435	435
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	155	155
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	456	456
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	456	456
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	418	418
* X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	5	5

FILE NAME: P:\2009\VEP0906-Var-Vor-Ph11\CADD\W09_IL126\Shts\03-D168J95-sht-IL126-S00.dgn
USER NAME: Millennium Professional Services



200 22ND Street, Suite 216, Lombard, IL 60148
630.705.8110 voice, 630.839.2566 fax
www.mps-il.com

MILLENNIA PROFESSIONAL SERVICES

DESIGNED -	CJD	REVISED -	
DRAWN -	CJD	REVISED -	
CHECKED -	RPD	REVISED -	
DATE -	2/15/2010	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ILLINOIS ROUTE 126
COUNTY LINE ROAD TO WALLIN DRIVE

SUMMARY OF QUANTITIES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0379	119 RS-14	WILL	20	3
CONTRACT NO. 60J95				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

SCALE: NTS SHEET NO. OF SHEETS STA. TO STA.

P:\2009\VEP0906-Var-Vor-Ph11\CADD\W09_IL126\Shts\03-D168J95-sht-IL126-S00.dgn