

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I 000					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I 000				
20201006	GRADING AND SHAPING SHOULDERS	UNIT	96	96					*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	544.5	544.5				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	37	37					*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	31915	31915				
21400100	GRADING AND SHAPING DITCHES	FOOT	1000	1000					*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2431	2431				
25200110	SODDING, SALT TOLERANT	SO YD	37	37					*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	833	833				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	22	22					*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	155	155				
40600300	AGGREGATE (PRIME COAT)	TON	107	107					*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	415	415				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	40	40					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	278	278				
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1105	1105					*88600600	DETECTOR LOOP REPLACEMENT	FOOT	958	958				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					X0322256	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	140	140					Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	13	13				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2250	2250													
42001300	PROTECTIVE COAT	SO YD	73	73													
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	26790	26790													
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	220	220													
44201851	CLASS D PATCHES, TYPE II, 17 INCH	SO YD	570	570													
44201855	CLASS D PATCHES, TYPE III, 17 INCH	SO YD	320	320													
44201857	CLASS D PATCHES, TYPE IV, 17 INCH	SO YD	160	160													
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1755	1755													
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	1	1													
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	2	2													
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	12	12													
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3													
67100100	MOBILIZATION	L SUM	1	1													
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1													
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1													
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1751	1751													
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	544.5	544.5													
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	31915	31915													
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2431	2431													
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	833	833													
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	155	155													

\*Specialty Items

Rev.

FILE NAME =	USER NAME = gorenoutab	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL ROUTE 176 (IL 60 /83 TO MIDLOTHIAN RD) SUMMARY OF QUANTITIES				F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pw\work\p\1001\gorenoutab\077846\DI31910-stf-pln.dgn		DRAWN -	REVISED -						1238	144 X-RS-6	LAKE	20	3
PLOT SCALE = 50,000' / IN.		CHECKED -	REVISED -						CONTRACT NO. 60J97				
PLOT DATE = 2/2/2010		DATE -	REVISED -						FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				
				SCALE: SHEET NO. OF SHEETS STA. TO STA.									