

SUMMARY OF QUANTITIES			80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT		URBAN 1000-2A						URBAN 1000-2A						
20201006	GRADING AND SHAPING SHOULDERS	UNIT	76	76												
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	50	50												
25200110	SODDING, SALT TOLERANT	SQ YD	50	50												
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	37	37												
40600300	AGGREGATE (PRIME COAT)	TON	188	188												
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	40	40												
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2770	2770												
40600895	CONSTRUCTING TEST STRIP	EACH	2	2												
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	172	172												
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	1210	1210												
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	52	52												
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	7230	7230												
42001300	PROTECTIVE COAT	SQ YD	100	100												
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	29300	29300												
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	150	150												
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	300	300												
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	222	222												
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	1464	1464												
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	17	17												
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	34	34												
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	305	305												
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	10	10												
60404950	FRAMES AND GRATES, TYPE 24	EACH	1	1												
64200105	SHOULDER RUMBLE STRIP	FOOT	2000	2000												
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6												
67100100	MOBILIZATION	L SUM	1	1												
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1												
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1												
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1												
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1												
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1												
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1												
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2	2												
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	9000	9000												
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1711	1711												
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	37500	37500												
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	8600	8600												
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	1300	1300												
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1375	1375												
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	680	680												
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1000	1000												
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1711	1711												
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	37500	37500												
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	8600	8600												
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1300	1300												
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1375	1375												
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	680	680												
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	400	400												
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	395	395												
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	3209	3209												
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4												
X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	6405	6405												
X4421000	PARTIAL DEPTH PATCHING	TON	280	280												
X4422030	PARTIAL DEPTH REMOVAL 3"	SQ YD	1602	1602												
Z0018400	DRAINAGE STRUCTURES TO BE ADJUSTED	EACH	35	35												
Δ Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	40	40												
Z0018600	DRAINAGE STRUCTURES TO BE RECONSTRUCTED	EACH	1	1												
© 2007 600 TRAINEE'S										Hour	500	500				

* SPECIALTY ITEMS
NON-PARTICIPATING
© Y080

FILE NAME =	USER NAME = strantab	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				SUMMARY OF QUANTITIES BARRINGTON ROAD, SO IL 62 TO I-90				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.			
es:\pw_wor\p\w\dot\strantab\0102835\0132010-str-plot.rgn		DRAWN -	REVISED -					SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	362	0608 RS-5	COOK	25	3	
		CHECKED -	REVISED -					FED. ROAD DIST. NO. 1 [ILLINOIS] FED. AID PROJECT											
		DATE -	REVISED -					CONTRACT NO. 60J98											