

SUMMARY OF QUANTITIES			URBAN CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			URBAN CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	80% FED. 20% STATE 1000	100% CITY 1000	50% CITY 50% STATE 1000		CODE NO	ITEM	UNIT	TOTAL QUANTITIES	80% FED. 20% STATE 1000	100% CITY 1000	50% CITY 50% STATE 1000	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	80	60	20			70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1			
25200110	SODDING, SALT TOLERANT	SO YD	80	60	20			70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4309	4309			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	30	29		1		70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	372	372			
40600300	AGGREGATE (PRIME COAT)	TON	148	138		10		70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	8085	8085			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	56	52		4		70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	5400	5400			
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1518	1414		104		70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	147	147			
40600895	CONSTRUCTING TEST STRIP	EACH	2	2				70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	53	53			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	735	735				70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	498	498			
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	421	421				70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1437	1437			
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	3606	3360		246		78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	372	372			
42001300	PROTECTIVE COAT	SO YD	267	200	67			78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	8085	8085			
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SO YD	25	25				78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	5443	5443			
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	1125	1125				78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	147	147			
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	36793	34286		2507		78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	53	53			
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	25	25				78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	498	498			
44000600	SIDEWALK REMOVAL	SO FT	1125	1125				78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	359	359			
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1200	900	300			78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	285	285			
44002217	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4 1/4"	SO YD	1770	1770				X0322256	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4			
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	884	884				Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	5	5			
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	368	368				Z0076600	TRAINEES	HOUR	500	500			
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	221	221											
55039700	STORM SEWERS TO BE CLEANED	FOOT	800	800											
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	7	5		2									
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	92	92											
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	5	5											
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	10	10											
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6											
67100100	MOBILIZATION	L SUM	1	1											
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1											
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1											

• DENOTES SPECIALTY ITEM  
 Δ Non-participating  
 © Y880