

SUMMARY OF QUANTITIES			URBAN CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT	TOTAL QUANTITIES 100% STATE	1000					CODE NO	ITEM	UNIT	TOTAL QUANTITIES						
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	14	14														
40600300	AGGREGATE (PRIME COAT)	TON	68	68														
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	51	51														
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	1011	1011														
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3772	3772														
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	33676	33676														
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6														
67100100	MOBILIZATION	L SUM	1	1														
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	8504	8504														
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	2835	2835														
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	100	100														
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	44492	44492														
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1000	1000														
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	100	100														
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	100	100														
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	452	452														
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	452	452														
*88600600	DETECTOR LOOP REPLACEMENT	FOOT	150	150														
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	360	360														
* SPECIALTY ITEM																		