

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT	TOTAL QUANTITIES						CODE NO	ITEM	UNIT	TOTAL QUANTITIES							
			1000																
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	10	10															
40600300	AGGREGATE (PRIME COAT)	TON	49	49															
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	37	37															
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	733	733															
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2734	2734															
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	24403	24403															
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6															
67100100	MOBILIZATION	L SUM	1	1															
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	6452	6452															
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	2151	2151															
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	100	100															
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	38340	38340															
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1295	1295															
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	200	200															
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	175	175															
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	775	775															
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	775	775															
*88600600	DETECTOR LOOP REPLACEMENT	FOOT	225	225															
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	566	566															
* SPECIALTY ITEM																			

FILE NAME = c:\pw\work\pwl\greendp\d0183613\Design.dgn	USER NAME = wllgreendp	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				SUMMARY OF QUANTITIES				F.A. - RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.			
		DRAWN -	REVISED -									VAR.	2010-011 RS	KANE	26	3			
		CHECKED -	REVISED -													CONTRACT NO. 60K30			
		DATE -	REVISED -									SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT	