ROUTE: IL 25 (Johnor Ave. to Hammond Ave.)

CROSS STREETS FROM	TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
Johnor		NB		2	300	600	67
		NB		12	4	48	5
	Country Club	NB		12	25	300	33
Country Club		NB		2	20	40	4
		NB		12	4	48	5
		NB	Edge	6	15	90	10
	Army Trail	NB		2	40	80	9
Army Trail	Seminary Rd.	NB		0	0	0	0
Seminary Rd.	Carl Lee Rd.	NB		12	4	48	5
Carl Lee Rd.	Hickory Lane	NB		0	0	0	0
Hickory Lane		NB		12	4	48	5
		NB		12	4	48	5
		NB		2	5	10	1
		NB		6	20	120	13
		NB		12	4	48	5
		NB		12	10	120	13
		NB		6	10	60	7
		NB		6	4	24	3
		NB		6	10	60	7
		NB		6	10	60	7
		NB		6	15	90	10
	Gilberts	NB		2	25	50	6
Gilberts	Dunham	NB		0	0	0	0
Dunham		NB		12	20	240	27
		NB		12	4	48	5
		NB		12	4	48	5
		NB		12	4	48	5
		NB		12	4	48	5
		NB		12	30	360	40
		NB		12	20	240	27
		NB		2	100	200	22
		NB		2	200	400	44
		NB		2	75	150	17
	West Bartlett	NB		2	6	12	1
West Bartlett		NB		2	6	12	1
		NB		2	6	12	1
		NB		2	6	12	1
		NB		12	6	72	8
		NB		2	6	12	1
		NB		2	125	250	28
		NB		12	4	48	5
		NB		2	200	400	44
	Hammond	NB	1	12	4	48	5

ROUTE: IL 25 (Johnor Ave. to Hammond Ave.)

CROSS STREETS FROM	TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
Hammond		SB		2	6	12	1
		SB		2	6	12	1
		SB		2	200	400	44
		SB		2	20	40	4
		SB		2	30	60	7
		SB		12	4	48	5
	West Bartlett	SB		12	4	48	5
West Bartlett		SB		12	12	144	16
	Dunham	SB		12	20	240	27
Dunham		SB		2	30	60	7
	Gilberts	SB		12	4	48	5
Gilberts		SB		12	4	48	5
		SB		12	8	96	11
	Hickory	SB		12	4	48	5
Hickory		SB		12	4	48	5
		SB		2	15	30	3
		SB		2	15	30	3
	Carl Lee Rd.	SB		12	4	48	5
Carl Lee Rd.	Seminary Rd.	SB		0	0	0	0
Seminary Rd.		SB		2	50	100	11
		SB		2	50	100	11
	Army Trail Rd.	SB		2	20	40	4
Army Trail Rd.		SB		2	15	30	3
		SB		2	40	80	9
		SB		2	10	20	2
		SB		12	4	48	5
		SB		12	10	120	13
		SB		2	15	30	3
		SB		12	4	48	5
		SB		12	4	48	5
		SB		2	25	50	6
		SB		12	4	48	5
		SB		2	50	100	11
	County Club Rd.	SB		12	4	48	5
Country Club Rd.	Johnor Rd.	SB		12	10	120	13
		TOTALS:			**2068**		**794**
					FT		**SY**

FILE NAME = c:\pw_work\PWIDOT\WILGREENDP\d0183613\Design.dgn	USER NAME = wilgreendp	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 2/20/2010	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
IL 25

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2010-011 RS	KANE	26	6
		CONTRACT NO. 60K30		

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT

Design.dgn 2/20/2010 2:27:37 PM User=wilgreendp