

ROUTE: US 30 (Griffin Dr. to Dickson Rd.)							
CROSS STREETS		DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	TO	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA
		(NB/SB)	(1, 2, 3)	WIDTH	LENGTH	(SQ FT)	(SQ YD)
1000 ft E of Prescott	Prescott Dr	WB		12	40	480	53
		WB		12	25	300	33
<b>TOTALS:</b>						<b>65</b>	<b>87</b>
						<b>FT</b>	<b>SY</b>

ROUTE: US 30 (US 34 to Harvey Rd.)							
CROSS STREETS		DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	TO	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA
		(NB/SB)	(1, 2, 3)	WIDTH	LENGTH	(SQ FT)	(SQ YD)
US 34		SB	1	12	12	144	16
		NB	1	6	10	60	7
		NB	1	12	160	1920	213
		NB	1	12	360	4320	480
	HARVEY	NB	1	12	360	4320	480
<b>TOTALS:</b>						<b>902</b>	<b>1196</b>
						<b>FT</b>	<b>SY</b>

FILE NAME =	USER NAME = wilgreendp	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>PATCHING SCHEDULE US 30</b>			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct\pwwork\pwwid\WILGREENDP\d0183613\d0183613.dgn	DESIGNED -	REVISED -	VAR.					2010-011 RS	KANE	26	18	
PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -	SCALE: SHEET NO. OF SHEETS STA. TO STA.			FED. ROAD DIST. NO. 1 [ILLINOIS] FED. AID PROJECT						
PLOT DATE = 2/20/2010	DATE -	REVISED -				CONTRACT NO. 60K30						