ROUTE: IL 31 (Webster St. to Fox Valley Sanitary District)

CROSS STREETS FROM	TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
WEBSTER		SB	1,2	24	12	288	32
		SB	1	12	10	120	13
		SB	1,2	24	12	288	32
		SB	2	12	10	120	13
		SB	1,2,3	36	12	432	48
		SB	1	6	150	900	100
		SB	2	6	100	600	67
		SB	3	6	200	1200	133
		SB	1	6	200	1200	133
		SB	1	12	8	96	11
		SB	2	12	8	96	11
	BRIDGE S. CATERPILAR	SB	1	12	10	120	13
SANITARY	BRIDGE	NB	1,2	24	10	240	27
		NB	1,2	24	10	240	27
		NB	1,2	24	8	192	21
		NB	1,2	24	8	192	21
		NB	1,2	24	8	192	21
		NB	1,2	24	8	192	21
		NB	1,2	24	8	192	21
		NB	1,2	24	8	192	21
		NB	1,2	24	8	192	21
		NB	1,2	24	8	192	21
		NB	1	4	420	1680	187
		NB	1,2	24	8	192	21
		NB	1,2	24	8	192	21
		NB	1,2	24	8	192	21
		NB	1,2	24	8	192	21
		NB	1,2	24	8	192	21
		NB	1,2	24	8	192	21
		NB	1,2	24	8	192	21
		NB	1,2	24	12	288	32
		NB	1,2	24	12	288	32
		NB	2	6	200	1200	133
		NB	2	12	200	2400	267
		NB	1,2	24	12	288	32
		NB	2	12	100	1200	133
		NB	1	12	10	120	13
		NB	2	12	250	3000	333
		NB	2	12	100	1200	133
		NB	1,2,3	36	12	432	48
		NB	1,2,3	36	12	432	48
		NB	1	6	100	600	67
		NB	1	12	12	144	16
		NB	1,2	24	200	4800	533
		NB	2	12	12	144	16
		TOTALS:			**2544**		**3025**
					FT		**SY**

FILE NAME = c:\pw_work\PWIDOT\WILGREENDP\d0183613\Design.dgn	USER NAME = wilgreendp	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 2/20/2010	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
IL 31

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2010-011 RS	KANE	26	19

CONTRACT NO. 60K30

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT

Design.dgn 2/20/2010 2:29:12 PM User=wilgreendp