

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT	TOTAL QUANTITIES						CODE NO	ITEM	UNIT	TOTAL QUANTITIES							
			1000																
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	18	18															
40600300	AGGREGATE (PRIME COAT)	TON	90	90															
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	67	67															
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	1340	1340															
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	5001	5001															
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	44644	44644															
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6															
67100100	MOBILIZATION	L SUM	1	1															
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	0.5	0.5															
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	10522	10522															
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	3508	3508															
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	100	100															
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	24481	24481															
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3304	3304															
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	140	140															
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	468	468															
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1335	1335															
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1335	1335															
*88600600	DETECTOR LOOP REPLACEMENT	FOOT	2129	2129															
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	1902	1902															
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1															
* SPECIALTY ITEM																			

Design.dgn 2/19/2010 9:27:08 AM User=wlgreendp