

ROUTE: IL 68 at IL 53 Bridge

CROSS STREETS		DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	TO	(EB/WB) (NB/SB)	NO. (1, 2, 3)	PATCH WIDTH	PATCH LENGTH	AREA (SQ FT)	AREA (SQ YD)
SB Off Ramp	Rte 53 Overpass	EB	1	12	10	120	13
SB Off Ramp	Rte 53 Overpass	EB	1	12	2	24	3
SB Off Ramp	Rte 53 Overpass	EB	2	12	10	120	13
SB Off Ramp	Rte 53 Overpass	EB	2	12	2	24	3
SB Off Ramp	Rte 53 Overpass	EB	2	2	2	4	0
SB Off Ramp	Rte 53 Overpass	EB	2	2	6	12	1
SB Off Ramp	Rte 53 Overpass	EB	2	2	4	8	1
Rte 53 Overpass	Wilke	EB	1	12	100	1200	133
Rte 53 Overpass	Wilke	EB	1	12	4	48	5
Rte 53 Overpass	Wilke	EB	Lt Turn	12	4	48	5
Rte 53 Overpass	Wilke	EB	2	12	100	1200	133
Rte 53 Overpass	Wilke	EB	2	12	4	48	5
Rte 53 Overpass	Wilke	EB	2	3	100	300	33
Rte 53 Overpass	Wilke	EB	2	3	25	75	8
Rte 53 Overpass	Wilke	EB	2	3	40	120	13
Wilke	Rte 53 Overpass	WB	2	2	50	100	11
Wilke	Rte 53 Overpass	WB	2	2	75	150	17
Wilke	Rte 53 Overpass	WB	2	2	200	400	44
Wilke	Rte 53 Overpass	WB	2	2	100	200	22
Wilke	Rte 53 Overpass	WB	2	6	80	480	53
Wilke	Rte 53 Overpass	WB	2	12	20	240	27
Wilke	Rte 53 Overpass	WB	1	12	2	24	3
Wilke	Rte 53 Overpass	WB	1	12	2	24	3
Wilke	Rte 53 Overpass	WB	1	12	2	24	3
Wilke	Rte 53 Overpass	WB	1	12	2	24	3
Wilke	Rte 53 Overpass	WB	1	12	20	240	27
Rte 53 Overpass	SB Rte 53 Off Ramp	WB	1	12	2	24	3
Rte 53 Overpass	SB Rte 53 Off Ramp	WB	Rt Turn	12	2	24	3
Rte 53 Overpass	SB Rte 53 Off Ramp	WB	Rt Turn	6	10	60	7
Rte 53 Overpass	SB Rte 53 Off Ramp	WB	2	12	2	24	3
Rte 53 Overpass	SB Rte 53 Off Ramp	WB	2	2	6	12	1
TOTALS:						988	600
						FT	SY

ROUTE: IL 68 (Baldwin Ave. to Wilke Rd.)

CROSS STREETS		DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	TO	(EB/WB) (NB/SB)	NO. (1, 2, 3)	PATCH WIDTH	PATCH LENGTH	AREA (SQ FT)	AREA (SQ YD)
At 1155 Dundee Rd		E/B	1	12	2	24	3
			2	12	2	24	3
		W/B	1	12	2	24	3
			2	12	2	24	3
			3	12	2	24	3
	W/B Between L1 & L2		1&2	100	2	200	22
IL-68 at IL-53 Ext Ramp		W/B	L2&Ramp	4	80	320	36
IL-68 E. of Baldwin		W/B	3	12	2	24	3
			3	12	2	24	3
			3	12	2	24	3
			2	12	2	24	3
			2	12	2	24	3
			L2&L3	2	50	100	11
IL-68 West of Baldwin		W/B	L1&L2	2	250	500	56
			L2&L3	2	200	400	44
IL-68 at Wilke Rd		E/B	L2	3	15	45	5
				3	35	105	12
TOTALS:						652	212
						FT	SY