ROUTE: IL 68 (Barrington Rd. to Hicks Rd.)

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
Quentin Rd.	Smith Rd.	EB	1	12	10	120	13
Quentin Rd.	Smith Rd.	EB	1	4	75	300	33
Quentin Rd.	Smith Rd.	EB	1	4	100	400	44
Quentin Rd.	Smith Rd.	EB	1	12	6	72	8
Quentin Rd.	Smith Rd.	WB	1	12	2	24	3
Quentin Rd.	Smith Rd.	WB	1	12	2	24	3
Quentin Rd.	Smith Rd.	WB	1	12	2	24	3
Quentin Rd.	Smith Rd.	WB	1	12	2	24	3
Quentin Rd.	Smith Rd.	WB	1	12	2	24	3
Smith Rd.	Peppermint Rd.	EB	1	4	100	400	44
Smith Rd.	Peppermint Rd.	EB	1	6	20	120	13
Smith Rd.	Peppermint Rd.	EB	1	6	20	120	13
Smith Rd.	Peppermint Rd.	EB	1	6	20	120	13
Smith Rd.	Peppermint Rd.	EB	1	12	15	180	20
Smith Rd.	Peppermint Rd.	EB	1	12	4	48	5
Smith Rd.	Peppermint Rd.	EB	1	12	50	600	67
Smith Rd.	Peppermint Rd.	EB	1	12	6	72	8
Smith Rd.	Peppermint Rd.	EB	1	4	20	80	9
Smith Rd.	Peppermint Rd.	EB	1	4	20	80	9
Smith Rd.	Peppermint Rd.	EB	1	4	20	80	9
Smith Rd.	Peppermint Rd.	EB	1	8	60	480	53
Smith Rd.	Peppermint Rd.	EB	1	12	6	72	8
Smith Rd.	Peppermint Rd.	WB	1	2	50	100	11
Peppermint Rd.	Hicks Rd.	EB	1	6	15	90	10
Peppermint Rd.	Hicks Rd.	EB	1	6	100	600	67
Peppermint Rd.	Hicks Rd.	EB	1	12	2	24	3
Peppermint Rd.	Hicks Rd.	EB	1	12	2	24	3
Peppermint Rd.	Hicks Rd.	EB	1	12	2	24	3
Peppermint Rd.	Hicks Rd.	EB	1	12	2	24	3
Peppermint Rd.	Hicks Rd.	EB	1	12	2	24	3
Peppermint Rd.	Hicks Rd.	EB	1	12	2	24	3
Peppermint Rd.	Hicks Rd.	EB	1	12	2	24	3
Peppermint Rd.	Hicks Rd.	EB	1	12	2	24	3
Peppermint Rd.	Hicks Rd.	EB	1	4	200	800	89
Peppermint Rd.	Hicks Rd.	EB	1	5	300	1500	167
Peppermint Rd.	Hicks Rd.	EB	1	12	2	24	3
Peppermint Rd.	Hicks Rd.	EB	1	12	2	24	3
Peppermint Rd.	Hicks Rd.	EB	1	12	2	24	3
Peppermint Rd.	Hicks Rd.	EB	1	12	2	24	3
Peppermint Rd.	Hicks Rd.	EB	1	3	100	300	33
Peppermint Rd.	Hicks Rd.	EB	1	3	15	45	5
Peppermint Rd.	Hicks Rd.	EB	1	6	150	900	100
Peppermint Rd.	Hicks Rd.	WB	1	12	2	24	3
Peppermint Rd.	Hicks Rd.	WB	1	4	50	200	22
Peppermint Rd.	Hicks Rd.	WB	1	12	2	24	3
Peppermint Rd.	Hicks Rd.	WB	1	12	100	1200	133
Peppermint Rd.	Hicks Rd.	WB	1	2	50	100	11
Peppermint Rd.	Hicks Rd.	WB	1	12	50	600	67
Peppermint Rd.	Hicks Rd.	WB	1	2	100	200	22
Peppermint Rd.	Hicks Rd.	WB	1	2	100	200	22
Peppermint Rd.	Hicks Rd.	WB	1	2	100	200	22
Peppermint Rd.	Hicks Rd.	WB	Rt turn	2	300	600	67
Peppermint Rd.	Hicks Rd.	WB	2	2	12	24	3
		TOTALS:			9189 FT		6506 SY

ROUTE: IL 68 at US 12 Intersection

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
East Leg(Turn Bay)	Intersection	WB	1	12	2	24	3
East Leg(Turn Bay)	Intersection	WB	2	12	2	24	3
East Leg(Turn Bay)	Intersection	EB	1	12	2	24	3
East Leg(Turn Bay)	Intersection	EB	1	12	20	240	27
East Leg(Turn Bay)	Intersection	EB	2	12	2	24	3
East Leg(Turn Bay)	Intersection	EB	2	12	2	24	3
East Leg(Turn Bay)	Intersection	EB	2	12	20	240	27
Intersection	West Leg(Turn Bay)	WB	1	12	2	24	3
Intersection	West Leg(Turn Bay)	WB	1	12	2	24	3
Intersection	West Leg(Turn Bay)	WB	2	12	2	24	3
Intersection	West Leg(Turn Bay)	WB	2	12	2	24	3
Intersection	West Leg(Turn Bay)	WB	2	12	2	24	3
Intersection	West Leg(Turn Bay)	EB	Lt Turn	12	2	24	3
Intersection	West Leg(Turn Bay)	EB	Lt Turn	12	2	24	3
Intersection	West Leg(Turn Bay)	EB	1	12	2	24	3
Intersection	West Leg(Turn Bay)	EB	2	12	2	24	3
South Leg(Turn bay)	Intersection	NB	1	12	2	24	3
South Leg(Turn bay)	Intersection	NB	1	12	2	24	3
South Leg(Turn bay)	Intersection	NB	1	2	100	200	22
South Leg(Turn bay)	Intersection	NB	Lt Turn	12	2	24	3
South Leg(Turn bay)	Intersection	NB	Lt Turn	12	2	24	3
South Leg(Turn bay)	Intersection	NB	1	12	2	24	3
South Leg(Turn bay)	Intersection	NB	1	12	2	24	3
South Leg(Turn bay)	Intersection	NB	1	2	100	200	22
South Leg(Turn bay)	Intersection	NB	2	12	2	24	3
South Leg(Turn bay)	Intersection	NB	2	12	2	24	3
South Leg(Turn bay)	Intersection	NB	2	2	125	250	28
South Leg(Turn bay)	Intersection	NB	2	12	10	120	13
South Leg(Turn bay)	Intersection	SB	1	12	2	24	3
South Leg(Turn bay)	Intersection	SB	1	12	10	120	13
South Leg(Turn bay)	Intersection	SB	1	12	2	24	3
South Leg(Turn bay)	Intersection	SB	1	12	2	24	3
South Leg(Turn bay)	Intersection	SB	1	12	2	24	3
South Leg(Turn bay)	Intersection	SB	2	4	40	160	18
South Leg(Turn bay)	Intersection	SB	2	4	5	20	2
South Leg(Turn bay)	Intersection	SB	2	2	2	4	0
South Leg(Turn bay)	Intersection	SB	2	12	2	24	3
South Leg(Turn bay)	Intersection	SB	2	12	10	120	13
South Leg(Turn bay)	Intersection	SB	2	12	2	24	3
South Leg(Turn bay)	Intersection	SB	2	12	2	24	3
South Leg(Turn bay)	Intersection	SB	2	12	2	24	3
South Leg(Turn bay)	Intersection	SB	2	4	10	40	4
Intersection	North leg(Turn Bay)	NB	1	12	2	24	3
Intersection	North leg(Turn Bay)	NB	1	12	2	24	3
Intersection	North leg(Turn Bay)	NB	2	12	2	24	3
Intersection	North leg(Turn Bay)	NB	2	12	2	24	3
Intersection	North leg(Turn Bay)	NB	2	2	15	30	3
Intersection	North leg(Turn Bay)	NB	2	12	2	24	3
Intersection	North leg(Turn Bay)	SB	1	12	2	24	3
Intersection	North leg(Turn Bay)	SB	1	12	2	24	3
Intersection	North leg(Turn Bay)	SB	Lt Turn	12	2	24	3
Intersection	North leg(Turn Bay)	SB	Lt Turn	12	2	24	3
Intersection	North leg(Turn Bay)	SB	2	12	2	24	3
Intersection	North leg(Turn Bay)	SB	2	12	2	24	3
Intersection	North leg(Turn Bay)	SB	2	2	15	30	3
SEB US 12 to SE of IL 68	Intersection (Winslowe)	S/E	L1	12	12	144	16
			L2	12	10	120	13
			L2	12	12	144	16
			L1	12	2	24	3
			L2	12	2	24	3
		TOTALS:			600 FT		354 SY