ROUTE: Lawrence Ave. (Cumberland Ave. to Harlem Ave.)

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
Prospect	Canfield	EB	1	3	600	1,800	200
		EB	1 & 2	6	200	1,200	133
Canfield	Overhill	EB	2	4	1000	4,000	444
		EB	2	4	600	2,400	267
		EB	2	4	200	800	89
Overhill	Oketo	EB	2	4	300	1,200	133
		EB	2	4	600	2,400	267
		EB	2	4	100	400	44
		EB	2	4	60	240	27
Oketo	Overhill	WB	1	4	200	800	89
		WB	CURB	4	300	1,200	133
		WB	1	4	300	1,200	133
		WB	2	4	100	400	44
Overhill	Canfield	WB	2	4	80	320	36
		WB	2	4	50	200	22
		WB	2	4	68	272	30
Canfield	Prospect	WB	2	4	20	80	9
		WB	1	4	250	1,000	111
		WB	1	4	250	1,000	111
		WB	1	4	120	480	53
		WB	2	4	50	200	22
		WB	2	4	60	240	27
Prospect	Cumberland	WB	1	4	50	200	22
		WB	2	4	150	600	67
		WB	1	4	50	200	22
Cumberland	Thatcher	EB	1 & 2	24	6	144	16
		EB	1 & 2	24	6	144	16
Thatcher	Prospect	EB	1 & 2	24	6	144	16
		EB	1 & 2	24	6	144	16
		EB	1 & 2	24	12	288	32
		EB	1 & 2	24	6	144	16
Prospect	Canfield	EB	1 & 2	24	6	144	16
		EB	1 & 2	24	12	288	32
		EB	1 & 2	24	6	144	16
		EB	1 & 2	24	12	288	32
		EB	1 & 2	24	8	192	21
		EB	1 & 2	24	10	240	27
		EB	1 & 2	24	6	144	16
		EB	1 & 2	24	6	144	16
		EB	1 & 2	24	8	192	21
		EB	1 & 2	24	8	192	21
		EB	1 & 2	24	6	144	16
		EB	1 & 2	24	6	144	16
		EB	1 & 2	24	8	192	21
		EB	1 & 2	24	6	144	16
		EB	1 & 2	24	6	144	16
		EB	1 & 2	24	6	144	16
Canfield	Overhill	EB	1 & 2	24	6	144	16
		EB	1 & 2	24	6	144	16
		EB	1 & 2	24	6	144	16
		EB	1 & 2	24	6	144	16
		EB	1 & 2	24	6	144	16
		EB	1 & 2	24	6	144	16
		EB	1 & 2	24	10	240	27
		EB	1 & 2	24	10	240	27
		EB	1 & 2	24	6	144	16
		EB	1 & 2	24	6	144	16
		EB	1 & 2	24	6	144	16
		EB	1 & 2	24	8	192	21
		EB	1 & 2	24	6	144	16
		EB	1 & 2	24	6	144	16

ROUTE: Lawrence Ave. (Cumberland Ave. to Harlem Ave.)

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
Canfield	Overhill	EB	1 & 2	24	8	192	21
		EB	1 & 2	24	8	192	21
		EB	1 & 2	24	6	144	16
		EB	1 & 2	24	8	192	21
		EB	1 & 2	24	6	144	16
		EB	1 & 2	24	6	144	16
		EB	1 & 2	24	6	144	16
Overhill	Oketo	EB	1 & 2	24	6	144	16
		EB	1 & 2	24	6	144	16
		EB	1 & 2	24	6	144	16
		EB	1 & 2	24	6	144	16
		EB	1 & 2	24	6	144	16
		EB	1 & 2	24	8	192	21
		EB	1 & 2	24	6	144	16
		EB	1 & 2	24	8	192	21
		EB	1 & 2	24	6	144	16
Thatcher	Canfield	WB	1 & 2	24	6	144	16
		WB	1 & 2	24	6	144	16
		WB	1 & 2	24	6	144	16
		WB	1 & 2	24	6	144	16
		WB	1 & 2	24	6	144	16
		WB	1 & 2	24	6	144	16
		WB	1 & 2	24	6	144	16
		WB	1 & 2	24	6	144	16
		WB	1 & 2	24	6	144	16
		WB	1 & 2	24	6	144	16
		WB	1 & 2	24	6	144	16
		WB	1 & 2	24	6	144	16
		WB	1 & 2	24	6	144	16
		WB	1 & 2	24	6	144	16
		WB	1 & 2	24	6	144	16
Canfield	Overhill	WB	1 & 2	24	6	144	16
		WB	1 & 2	24	6	144	16
		WB	1 & 2	24	6	144	16
		WB	1 & 2	24	8	192	21
		WB	1 & 2	24	8	192	21
		WB	1 & 2	24	6	144	16
		WB	1 & 2	24	6	144	16
		WB	1 & 2	24	6	144	16
		WB	1 & 2	24	6	144	16
		WB	1 & 2	24	6	144	16
		WB	1 & 2	24	10	240	27
		WB	1 & 2	24	8	192	21
		WB	1 & 2	24	6	144	16
		WB	1 & 2	24	6	144	16
		WB	1 & 2	24	8	192	21
		WB	1 & 2	24	6	144	16
		WB	1 & 2	24	8	192	21
		WB	1 & 2	24	6	144	16
		WB	1 & 2	24	6	144	16
		WB	1 & 2	24	6	144	16
		WB	1 & 2	24	6	144	16
Overhill	Oketo	WB	1 & 2	24	6	144	16
		WB	1 & 2	24	6	144	16
		WB	1 & 2	24	6	144	16
		WB	1 & 2	24	8	192	21
		WB	1 & 2	24	6	144	16
		WB	1 & 2	24	8	192	21
		WB	1 & 2	24	6	144	16
		WB	1 & 2	24	6	144	16
		WB	1 & 2	24	6	144	16
		TOTALS:			6402 FT		4254 SY

FILE NAME = c:\pw_work\pwidot\wilgreendp\d0183617\Design.dgn	USER NAME = wilgreendp	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 2/18/2010	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
LAWRENCE AVE.

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2010-013 RS	COOK	43	25
		CONTRACT NO. 60K32		

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT

Design.dgn 2/18/2010 4:32:01 PM User=wilgreendp