

ROUTE: River Rd. (Foster Ave. to Devon Ave.)

CROSS STREETS		DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT	PAVEMENT	REPAIR	REPAIR				
FROM	TO			PATCH WIDTH	PATCH LENGTH	AREA (SQ FT)	AREA (SQ YD)				
Foster Avenue	Devon Avenue	SB	2	2	50	100	11				
				10	12	120	13				
				10	12	120	13				
				10	12	120	13				
				10	12	120	13				
				10	12	120	13				
				10	12	120	13				
				10	12	120	13				
				10	12	120	13				
				2	50	100	11				
				10	12	120	13				
				3	50	150	17				
				10	12	120	13				
				10	12	120	13				
				10	12	120	13				
				Foster Avenue	Devon Avenue	NB	2	6	500	3000	333
6	50	300	33								
6	200	1200	133								
6	300	1800	200								
6	300	1800	200								
12	100	1200	133								
3	500	1500	167								
6	100	600	67								
3	100	300	33								
6	12	72	8								
3	200	600	67								
Foster Avenue	Devon Avenue	SB	1					10	12	120	13
								10	12	120	13
								12	200	2400	267
								6	300	1800	200
Foster Avenue	Devon Avenue	NB	1					6	300	1800	200
				12	200	2400	267				
				10	12	120	13				
				12	50	600	67				

TOTALS: 4772 FT 3364 SY

FILE NAME =	USER NAME = wlgreendp	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PATCHING SCHEDULE RIVER RD.	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ar\p\work\pwidot\wlgreendp\d0183617\De	DRAWN -	REVISED -	VAR.			2010-013 RS	COOK	43	29	
PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -	CONTRACT NO. 60K32							
PLOT DATE = 2/18/2010	DATE -	REVISED -	SCALE:			SHEET NO.	OF SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT