ROUTE: Cermak at 25th Ave. Frontage Rd. (N & S) (Barnsdale Rd. to 21st St.)

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
Frontage Rd. (WB) - 25th Ave.		EB/WB	1,2	20	6	120	13
		EB/WB	1,2	20	6	120	13
		EB/WB	1,2	20	6	120	13
		WB	1,2	20	6	120	13
		WB/EB	2	10	10	100	11
		WB/EB	1,2	20	6	120	13
		WB/EB	1,2	20	6	120	13
		WB/EB	2	4	4	16	2
		WB/EB	1,2	20	6	120	13
		WB/EB	1,2	20	6	120	13
		WB/EB	1,2	20	6	120	13
		WB/EB	1,2	20	6	120	13
		WB/EB	1,2	20	6	120	13
		WB/EB	1,2	20	6	120	13
		WB/EB	1,2	20	6	120	13
		WB/EB	1,2	20	6	120	13
		WB/EB	1,2	20	6	120	13
		WB/EB	1,2	20	6	120	13
		WB/EB	1,2	20	6	120	13
		WB/EB	1,2	20	6	120	13
		EB/WB	1,2	20	6	120	13
		EB/WB	1,2	20	6	120	13
		EB/WB	1,2	20	6	120	13
		EB/WB	1,2	20	6	120	13
		EB/WB	1,2	20	6	120	13
		EB/WB	1,2	10	6	60	7
		WB	1	10	10	100	11
		EB	1	20	6	120	13
		EB/WB	1,2	20	6	120	13
		EB/WB	1,2	20	6	120	13
		EB/WB	1,2	8	6	48	5
		EB	2	20	15	300	33
		EB/WB	1,2	20	6	120	13
		EB/WB	1,2	20	6	120	13
		EB/WB	1,2	20	6	120	13
		EB/WB	1,2	20	6	120	13
		EB/WB	1,2	20	6	120	13
		EB/WB	1,2	20	6	120	13
		EB/WB	1,2	20	6	120	13
		EB/WB	1,2	20	6	120	13
		EB/WB	1,2	20	6	120	13
		EB/WB	1,2	20	6	120	13
		EB/WB	1,2	20	6	120	13
		EB/WB	1,2	20	6	120	13
		EB/WB	1,2	20	6	120	13
		EB/WB	1,2	20	6	120	13
		EB	2	10	6	60	7
		EB	2	10	6	60	7
		TOTALS:			291 FT		589 SY

FILE NAME = c:\pw_work\PWIDOT\WILGREENDP\d0183621\Design.dgn	USER NAME = wilgreendp	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 2/20/2010	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
CERMAK RD.

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2010-014 RS	COOK	34	12
		CONTRACT NO. 60K33		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

Design.dgn 2/20/2010 8:27:00 AM User=wilgreendp