SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES (URBAN 100% STATE)	CONSTRUCTION TYPE CODE: COOK COUNTY 1000	WILL COUNTY 1000				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	11	9	2				
40600300	AGGREGATE (PRIME COAT)	TON	56	45	11				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	42	33	9				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	834	663	171				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3113	2476	637				
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	27786	22103	5683				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	5	1				
67100100	MOBILIZATION	L SUM	1	0.9	0.1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	6824	5066	1758				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2275	1689	586				
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	100	100					
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	34823	25223	9600				
*78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	1650		1650				
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	740	740					
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	100	100					
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	150	150					
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1118	956	162				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1118	956	162				
*88600600	DETECTOR LOOP REPLACEMENT	FOOT	675	500	175				
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	874	822	52				

* SPECIALTY ITEM

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					

FILE NAME = c:\pw_work\PWIDOT\WILGREENDP\d0183625\Designdgn	USER NAME = wilgreendp	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 2/19/2010	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2010-015 RS	COOK	26	3

CONTRACT NO. 60K34

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT

Design.dgn 2/19/2010 6:43:34 AM User=wilgreendp