ROUTE: 111th St (Ridgeland Ave. to Harlem Ave.)

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
Ridgeland		WB	2	12	12	144	16
		WB	2	12	12	144	16
		WB	2	6	100	600	67
		WB	2	6	12	300	33
		WB	2	6	50	300	33
		WB	2	12	12	144	16
		WB	2	12	12	144	16
		WB	2	12	12	144	16
		WB	2	6	50	300	33
	Harlem	WB	2	12	12	144	16
Harlem		EB	2	12	20	240	27
		EB	2	6	50	300	33
		EB	2	12	20	240	27
		EB	2	12	12	144	16
		EB	2	12	100	1200	133
		EB	2	12	50	300	33
		EB	2	6	50	300	33
		EB	2	12	20	240	27
		EB	2	12	12	144	16
		EB	2	6	100	600	67
		EB	2	6	100	600	67
		EB	2	12	12	144	16
		EB	2	12	50	600	67
		EB	2	12	12	144	16
		EB	2	12	50	600	67
		EB	2	12	20	240	27
	Ridgeland	EB	2	12	12	144	16
Ridgeland		WB	1	6	12	72	8
		WB	1	12	50	600	67
		WB	1	12	20	240	27
		WB	1	12	75	900	100
		WB	1	12	50	600	67
		WB	1	6	12	72	8
		WB	1	6	12	72	8
		WB	1	12	20	240	27
		WB	1	12	12	144	16
		WB	1	12	12	144	16
		WB	1	12	12	144	16
		WB	1	12	12	144	16
		WB	1	12	12	144	16
		WB	1	12	12	144	16
		WB	1	12	12	144	16
	Harlem	WB	1	12	15	180	20
Harlem		EB	1	6	12	72	8
		EB	1	12	12	144	16
		EB	1	12	12	144	16
		EB	1	12	12	144	16
		EB	1	12	12	144	16
		EB	1	12	12	144	16
		EB	1	12	12	144	16
		EB	1	12	12	144	16
		EB	1	12	12	144	16
		EB	1	12	75	900	100
		EB	1	12	12	144	16
		EB	1	12	12	144	16
		EB	1	12	15	180	20
	Ridgeland	EB	1	12	12	144	16
		TOTALS:			1558 FT		1696 SY

FILE NAME = c:\pw_work\PWIDOT\WILGREENDP\d0183625\Design.dgn	USER NAME = wilgreendp	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 2/17/2010	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
111TH ST.

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2010-015 RS	COOK	26	6

CONTRACT NO. 60K34

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT

Design.dgn 2/17/2010 6:12:54 PM User=wilgreendp