ROUTE: Torrence Ave. (Ridge Rd. to I-80/94)

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
178TH STREET	THORTON LANSING RD	SB	1	2	36	72	8
		SB	1	2	30	60	7
		SB	1	2	400	800	89
		SB	1	5	12	60	7
		SB	1	1	12	12	1
		SB	1	4	12	48	5
		SB	1	2	200	400	44
		SB	1	2	12	24	3
		SB	1	2	12	24	3
THORTON LANSING RD	RIDGE RD	SB	1	2	12	24	3
		SB	1	2	12	24	3
		SB	1	2	12	24	3
		SB	1	2	50	100	11
		SB	1	2	100	200	22
		SB	1	4	12	48	5
		SB	1	2	24	48	5
		SB	1	2	24	48	5
178TH STREET	THORTON LANSING RD	SB	2	4	30	120	13
178th / TORRENCE INTERSECTION		SB	2	4	14	56	6
		SB	2	2	400	800	89
		SB	2	12	12	144	16
		SB	2	4	50	200	22
		SB	2	2	12	24	3
		SB	2	2	20	40	4
		SB	2	2	15	30	3
		SB	2	4	12	48	5
THORTON LANSING RD	RIDGE RD	SB	2	2	12	24	3
		SB	2	2	12	24	3
		SB	2	1	8	8	1
		SB	2	2	12	24	3
		SB	2	4	4	16	2
		SB	2	4	4	16	2
		SB	2	2	2	4	0
		SB	2	4	12	48	5
		SB	2	4	4	16	2
		SB	2	4	4	16	2
		SB	2	4	4	16	2
		SB	2	2	4	8	1
		SB	2	2	8	16	2
BURGER KING RADIUS		SB	2	8	15	120	13
RIDGE RD	THORTON LANSING RD	NB	1	2	200	400	44
		NB	1	4	12	48	5
		NB	1	2	50	100	11
		NB	1	4	100	400	44
		NB	1	2	60	120	13
		NB	1	2	20	40	4
		NB	1	2	80	160	18

ROUTE: Torrence Ave. (Ridge Rd. to I-80/94)

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
RIDGE RD	THORTON LANSING RD	NB	1	2	12	24	3
		NB	1	2	12	24	3
		NB	1	4	12	48	5
		NB	1	12	12	144	16
		NB	1	2	60	120	13
		NB	1	2	12	24	3
		NB	1	2	12	24	3
		NB	1	2	12	24	3
		NB	1	2	12	24	3
		NB	1	2	12	24	3
		NB	1	2	12	24	3
		NB	1	2	12	24	3
		NB	1	2	12	24	3
		NB	1	2	12	24	3
		NB	1	2	12	24	3
		NB	1	2	12	24	3
		NB	1	2	50	100	11
RIDGE RD	THORTON LANSING RD	NB	2	12	60	720	80
		NB	2	4	60	240	27
		NB	2	12	40	480	53
		NB	2	2	100	200	22
		NB	2	4	20	80	9
		NB	2	4	12	48	5
		NB	2	2	12	24	3
		NB	2	3	30	90	10
		NB	2	2	6	12	1
		NB	2	4	50	200	22
		NB	2	2	20	40	4
		NB	2	2	10	20	2
		NB	2	4	12	48	5
		NB	2	6	12	72	8
		NB	2	4	10	40	4
		NB	2	2	8	16	2
THORTON LANSING RD	178TH STREET	NB	2	4	8	32	4
		NB	2	2	6	12	1
		NB	2	4	12	48	5
		NB	2	2	12	24	3
ALONG CL FROM 179TH TO NORTH LIMITS		NB	2	2	900	1800	200
		NB	2	4	12	48	5
		NB	2	2	12	24	3
		NB	2	4	50	200	22
		NB	2	4	50	200	22
		NB	2	4	30	120	13
		NB	2	2	10	20	2
		NB	2	4	50	200	22
		TOTALS:			4056 FT		1207 SY

FILE NAME = c:\pw_work\PWIDOT\WILGREENDP\d0183625\Design.dgn

USER NAME = wilgreendp | DESIGNED - | REVISED -
DRAWN - | REVISED -
PLOT SCALE = 100.0000 ' / IN. | CHECKED - | REVISED -
PLOT DATE = 2/17/2010 | DATE - | REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
TORRENCE AVE.

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2010-015 RS	COOK	26	16

CONTRACT NO. 60K34

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT

Design.dgn 2/17/2010 5:13:57 PM User=wilgreendp