

| | | | | |
|-----------------------|----------------|---------------------------|--------------|-----------|
| F.A.P. NO. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 1285 | 02-00075-00-PV | COOK | 161 | 7 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. . | | ILLINOIS FED. AID PROJECT | | |

SUMMARY OF QUANTITIES

| CODE NUMBER | PAY ITEM | UNIT | TOTAL QUANTITY | ROADWAY | ROADWAY | ROADWAY | TRAFFIC SIGNALS | TRAFFIC SIGNALS INTERCONNECT | LIGHTING | LOCAL LANDSCAPING | LOCAL WATER MAIN |
|-------------|---|--------|----------------|------------------------|----------------------------|---------------------------|----------------------------|------------------------------|---------------------------|-------------------|------------------|
| | | | | 100% FED- ARA | 80% FED- CMAO 20% LOCAL | 70% FED- STP 30% LOCAL | 80% FED- CMAO 20% LOCAL | 80% FED- CMAO 20% LOCAL | 70% FED- STP 30% LOCAL | 100% VILLAGE | 100% VILLAGE |
| | | | | CONSTRUCTION TYPE CODE | | | | | | | |
| | | | | I000-2A | I000-2A | I000-2A | Y031-1F | Y031-1F | Y030-1E | Y003 | Y060 |
| 60255500 | MANHOLES TO BE ADJUSTED | EACH | 6 | 6 | | | | | | | |
| 60260050 | SANITARY MANHOLES TO BE RECONSTRUCTED | EACH | 3 | | | 3 | | | | | |
| 60260100 | INLETS TO BE ADJUSTED | EACH | 1 | 1 | | | | | | | |
| • 60265700 | VALVE VAULTS TO BE ADJUSTED | EACH | 5 | | | | | | | | 5 |
| • 60266500 | VALVE VAULTS TO BE REMOVED | EACH | 3 | | | | | | | | 3 |
| 60500040 | REMOVING MANHOLES | EACH | 21 | 21 | | | | | | | |
| 60500050 | REMOVING CATCH BASINS | EACH | 17 | 17 | | | | | | | |
| 60500060 | REMOVING INLETS | EACH | 19 | 19 | | | | | | | |
| 60600605 | CONCRETE CURB, TYPE B | FOOT | 571 | 571 | | | | | | | |
| 60601005 | CONCRETE CURB, TYPE B (SPECIAL) | FOOT | 1,252 | 1,252 | | | | | | | |
| 60603800 | COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 | FOOT | 8,807 | 3,098 | 5,709 | | | | | | |
| 60618800 | CONCRETE MEDIAN, TYPE SB | SQ FT | 3,546 | 3,546 | | | | | | | |
| 60619600 | CONCRETE MEDIAN, TYPE SB-6.12 | SQ FT | 3,088 | 3,088 | | | | | | | |
| • 63000001 | STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS | FOOT | 55 | 55 | | | | | | | |
| • 66900105 | UNDERGROUND STORAGE TANK REMOVAL | EACH | 3 | | | 3 | | | | | |
| • 66900200 | NON-SPECIAL WASTE DISPOSAL | CU YD | 1,721 | | | 1,721 | | | | | |
| • 66900400 | SPECIAL WASTE GROUNDWATER DISPOSAL | GAL | 4,290 | | | 4,290 | | | | | |
| • 66900450 | SPECIAL WASTE PLANS AND REPORTS | L SUM | 1 | | | 1 | | | | | |
| • 66900530 | SOIL DISPOSAL ANALYSIS | EACH | 3 | | | 3 | | | | | |
| • 66901000 | BACKFILL PLUGS | CU YD | 45 | | | 45 | | | | | |
| 67000400 | ENGINEER'S FIELD OFFICE TYPE A | CAL MO | 18 | | | 18 | | | | | |
| 67100100 | MOBILIZATION | L SUM | 1 | | | 1 | | | | | |
| 70101800 | TRAFFIC CONTROL AND PROTECTION (SPECIAL) | L SUM | 1 | | | 1 | | | | | |
| 70101900 | TRAFFIC CONTROL AND PROTECTION (DETOUR 1) | L SUM | 1 | | | 1 | | | | | |
| 70102000 | TRAFFIC CONTROL AND PROTECTION (DETOUR 2) | L SUM | 1 | | | 1 | | | | | |
| 70103815 | TRAFFIC CONTROL SURVEILLANCE | CAL DA | 548 | | | 548 | | | | | |

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
 VILLAGE OF PALATINE
 PALATINE ROAD & PLUM GROVE ROAD RECONSTRUCTION
 SMITH STREET TO US 14 (NORTHWEST HIGHWAY)
 SUMMARY OF QUANTITIES
 VERT. SCALE: DRAWN BY BA
 HORIZ. SCALE: CHECKED BY
 DATE: OCTOBER 19, 2009

• - DENOTES SPECIALTY ITEMS

PLOT DATE = 08/04/09
 FILE NAME = 02-00075-00-PV
 USER NAME = MUSERN