

SUMMARY OF QUANTITIES

| CODE NUMBER | PAY ITEM | UNIT | TOTAL QUANTITY | ROADWAY | ROADWAY | ROADWAY | TRAFFIC SIGNALS | TRAFFIC SIGNALS INTERCONNECT | LIGHTING | LOCAL LANDSCAPING | LOCAL WATER MAIN |
|-------------|--|--------|----------------|------------------------|----------------------------|---------------------------|----------------------------|------------------------------|---------------------------|-------------------|------------------|
| | | | | 100% FED- ARA | 80% FED- CMAO 20% LOCAL | 70% FED- STP 30% LOCAL | 80% FED- CMAO 20% LOCAL | 80% FED- CMAO 20% LOCAL | 70% FED- STP 30% LOCAL | 100% VILLAGE | 100% VILLAGE |
| | | | | CONSTRUCTION TYPE CODE | | | | | | | |
| | | | | 1000-2A | 1000-2A | 1000-2A | Y031-1F | Y031-1F | Y030-1E | Y003 | Y060 |
| 70106800 | CHANGEABLE MESSAGE SIGN | CAL MO | 18 | | | 18 | | | | | |
| 70300500 | PAVEMENT MARKING TAPE, TYPE III | FOOT | 8,325 | | | 8,325 | | | | | |
| * 72000100 | SIGN PANEL - TYPE I | SQ FT | 427 | | | 340 | 87 | | | | |
| * 72900100 | METAL POST - TYPE A | FOOT | 1,050 | | | 1,050 | | | | | |
| * 78000100 | THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | 1,271 | | | 1,271 | | | | | |
| * 78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4" | FOOT | 11,156 | | | 11,156 | | | | | |
| * 78000400 | THERMOPLASTIC PAVEMENT MARKING - LINE 6" | FOOT | 5,398 | | | 5,398 | | | | | |
| * 78000600 | THERMOPLASTIC PAVEMENT MARKING - LINE 12" | FOOT | 207 | | | 207 | | | | | |
| * 78000650 | THERMOPLASTIC PAVEMENT MARKING - LINE 24" | FOOT | 574 | | | 574 | | | | | |
| * 78100100 | RAISED REFLECTIVE PAVEMENT MARKER | EACH | 295 | | | 295 | | | | | |
| 78300100 | PAVEMENT MARKING REMOVAL | SQ FT | 8,000 | | | 8,000 | | | | | |
| * 78300200 | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL | EACH | 60 | | | 60 | | | | | |
| * 80400100 | ELECTRIC SERVICE INSTALLATION | EACH | 2 | | | | | | 2 | | |
| * 80400200 | ELECTRIC UTILITY SERVICE CONNECTION | L SUM | 1 | | | | | | 1 | | |
| * 81000600 | CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL | FOOT | 1,341 | | | | 983 | 358 | | | |
| * 81000700 | CONDUIT IN TRENCH, 2 1/2 " DIA., GALVANIZED STEEL | FOOT | 111 | | | | 78 | | 33 | | |
| * 81000800 | CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL | FOOT | 171 | | | | 171 | | | | |
| * 81001000 | CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL | FOOT | 901 | | | | 10 | | 891 | | |
| * 81001100 | CONDUIT IN TRENCH, 5" DIA., GALVANIZED STEEL | FOOT | 10 | | | | 10 | | | | |
| * 81018500 | CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL | FOOT | 592 | | | | 445 | 147 | | | |
| * 81018700 | CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL | FOOT | 157 | | | | 157 | | | | |
| * 81018900 | CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL | FOOT | 1,759 | | | | 701 | | 1,058 | | |
| * 81400100 | HANDHOLE | EACH | 14 | | | | 14 | | | | |
| * 81400200 | HEAVY-DUTY HANDHOLE | EACH | 4 | | | | 4 | | | | |
| * 81400300 | DOUBLE HANDHOLE | EACH | 4 | | | | 4 | | | | |
| * 81701345 | ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE USE) 3-1/C NO. 3/0 | FOOT | 93 | | | | | | 93 | | |

* - DENOTES SPECIALTY ITEMS

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
 VILLAGE OF PALATINE
 PALATINE ROAD & PLUM GROVE ROAD RECONSTRUCTION
 SMITH STREET TO US 14 (NORTHWEST HIGHWAY)
 SUMMARY OF QUANTITIES
 SCALE: VERT. _____
 HORIZ. _____
 DATE: OCTOBER 19, 2009
 DRAWN BY: BA
 CHECKED BY: _____

DATE = #DATE#
 FILE NAME = #FILE#
 PLOT SCALE = #SCALE#
 USER NAME = #USER#