

TEMPORARY EMERGENCY VEHICLE PREEMPTION SEQUENCE OF OPERATION PRE-STAGE, STAGE I, STAGE II & FINAL STAGE

	1	5	5	8	8	11	11	14	18	18	22	22	26	26	PREEMPTOR NUMBER 3	PREEMPTOR NUMBER 4	CLEAR TO NORMAL SEQUENCE																	
CHANGE FROM NORMAL SEQUENCE OF OPERATION INTERVAL NUMBER	1A	1B	1C	1D	1E	1F	1G	1H	1J	1K	1L	1M	1N	1P	1Q	1R	1S	1T	1U	1V	1W	1X	1Y	1Z	1AA	1BB	1CC	1DD	1EE	1FF	2	3		
EMERGENCY VEHICLE PREEMPTION SEQUENCE OF OPERATION INTERVAL NUMBER	2 OR 3	1C	2	1E	1F	3	1H	2	1K	1L	3	2	1P	1Q	3	2 OR 3	1T	1U	2	1W	3	1Y	1Z	2	1BB	3	1DD	1EE	2	3			◇	
PALATINE ROAD FAR LEFT AND RIGHT SPAN WIRE SIGNALS E/B	R → Y	R	R	R	R	R	G → G	G → Y	G → G	Y	R	G	G	Y	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	G	R	◇
PALATINE ROAD NEAR RIGHT SPAN WIRE SIGNAL E/B	R	R	R	R	R	R	G	G	G	Y	R	G	G	Y	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	G	R	◇
PALATINE ROAD FAR LEFT AND RIGHT SPAN WIRE SIGNALS W/B	R → Y	G → G	G → Y	G → G	Y	R	R	R	R	R	R	G	G	Y	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	G	R	◇
PALATINE ROAD NEAR RIGHT SPAN WIRE SIGNAL W/B	R	G	G	G	Y	R	R	R	R	R	R	G	G	Y	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	G	R	◇
PLUM GROVE ROAD FAR LEFT AND RIGHT SPAN WIRE SIGNALS S/B	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	G	Y	R	G	G	G	Y	R	G	R	G	◇	
PLUM GROVE ROAD NEAR RIGHT SPAN WIRE SIGNAL S/B	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	G	Y	R	G	G	G	Y	R	G	R	G	◇	
PLUM GROVE ROAD FAR LEFT AND RIGHT SPAN WIRE SIGNALS N/B	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	G	Y	R	G	G	Y	R	G	R	G	◇		
PLUM GROVE ROAD NEAR RIGHT SPAN WIRE SIGNAL N/B	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	G	Y	R	G	G	Y	R	G	R	G	◇		
PEDESTRIAN SIGNALS CROSSING PLUM GROVE RD. ON NORTHSIDE OF PALATINE RD.	H	FH	H	FH	H	H	H	H	H	H	H	FH	FH	H	H	H	H	H	H	H	H	H	H	H	H	H	H	H	H	H	H	H	◇	
PEDESTRIAN SIGNALS CROSSING PLUM GROVE RD. ON SOUTHSIDE OF PALATINE RD.	H	H	H	H	H	H	FH	H	FH	H	H	FH	FH	H	H	H	H	H	H	H	H	H	H	H	H	H	H	H	H	H	H	H	◇	
PEDESTRIAN SIGNALS CROSSING PALATINE RD. ON EASTSIDE OF PLUM GROVE RD.	H	H	H	H	H	H	H	H	H	H	H	H	H	H	H	FH	H	H	FH	H	H	H	H	H	H	H	FH	H	H	FH	H	H	◇	
PEDESTRIAN SIGNALS CROSSING PALATINE RD. ON WESTSIDE OF PLUM GROVE RD.	H	H	H	H	H	H	H	H	H	H	H	H	H	H	H	H	H	H	H	H	H	FH	H	H	FH	H	FH	H	H	FH	H	H	◇	

◇ EMERGENCY VEHICLE SEQUENCE SHALL PROVIDE THE PROPER CLEARANCE INTERVAL TO RESUME THE NORMAL SEQUENCE OF OPERATION OR PROPER CLEARANCE INTERVAL TO DISPLAY A DIFFERENT EMERGENCY INTERVAL AFTER EMERGENCY VEHICLE INTERVAL 2 OR 3 IS TERMINATED.

P = ILLUMINATED PERSON = WALK  
 FH = ILLUMINATED FLASHING HAND = FLASHING DON'T WALK  
 H = ILLUMINATED SOLID HAND = DON'T WALK

PLOT DATE = #DATE#  
 PLOT SCALE = #SCALE#  
 USER NAME = #USER#

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION VILLAGE OF PALATINE PALATINE ROAD & PLUM GROVE ROAD RECONSTRUCTION SMITH STREET TO US 14 (NORTHWEST HIGHWAY) EMERGENCY VEHICLE PREEMPTION SEQUENCE OF OPERATION PRE-STAGE, STAGE I, STAGE II & FINAL STAGE CONSTRUCTION SCALE: NONE DRAWN BY: DMB DATE: OCTOBER 19, 2009 CHECKED BY: RY
NAME	DATE	